

- Rubber roof coating on northeast unit and 3 southeastern units
- Replace quantity of panel segments with color matching best possible
- Replace flashing with color matching best possible
- Replace corner segments with color matching best possible
- Touch up paint as needed
- Cable replacements as needed
- LED light ends
- Bolt replacement as needed
- Weather strip doors as needed
- Add unit signage

| T-HANGAR REHAB | | | | | | | | |
|----------------|-------|--------|---------|----------|---------------|---|----------------|------------------|
| ROW | BOLTS | PANELS | CORNERS | FLASHING | WEATHER STRIP | PAINT | LED WALL PACKS | DESIGNATION SIGN |
| D | 5 | 24 | 2 | 2 | 0 | 16' x 190' (x2) 6080 sq ft 14' x 48' (x2) 1344 sq ft | 2 | 2 |
| E | 0 | 4 | 0 | 0 | 0 | 0 | 2 | 2 |
| F | 19 | 9 | 3 | 1 | 0 | 1' x 190' (x4) 760 sq ft | 2 | 2 |
| G | 10 | 18 | 2 | 0 | 2 | 1' x 190' (x4) 760 sq ft | 2 | 2 |
| H | 7 | 21 | 1 | 0 | 0 | 1' x 260' (x2) 520 sq ft | 2 | 2 |
| Total | 41 | 76 | 8 | 3 | 2 | 9464 | 10 | 10 |

* The sections of paint needed are at the bottom 1 foot of the hangars and at the folding section of the doors. Very conservative estimate.

* Many of the panels are 2'x2' sections that need to be replaced at the bottom of the doors, not whole sections.

* No cables need to be replaced at this time.