

19-1193



Proposal


Gerke Excavating, Inc
 15341 State Hwy 131, S
 Tomah, WI 54660
 www.gerkeexcavating.com
 Phone (608) 372-4203
 Fax (608) 372-4139

To: City of La Crosse	Project: 28th Street Sanitary Sewer Repair La Crosse, WI	Proposal #: Q19440 Date: August 9, 2019
---------------------------------	---	--

Line Number	Item Number	Bid Item	Unit	Quantity	Unit Price	Total Cost	Notes per Item
1.0000	619.1000	Mobilization	Ea	1.00	\$ 7,307.96	\$ 7,307.96	
2.0000	204.0150	Removing Curb & Gutter	Lf	1,000.00	\$ 4.00	\$ 4,000.00	
3.0000	100.3500	Cut and Cap Watermain	Ea	2.00	\$ 5,149.60	\$ 10,299.20	
4.0000	813.0205	Connect Sanitary Sewer Main, (Various)	Ea	5.00	\$ 2,430.55	\$ 12,152.75	
5.0000	810.0104	Sanitary Sewer Pipe Schedule 35, 4"	Lf	114.00	\$ 51.66	\$ 5,889.24	
6.0000	810.0108	Sanitary Sewer Pipe Schedule 26, 8"	Lf	98.00	\$ 61.40	\$ 6,017.20	
7.0000	810.0110	Sanitary Sewer Pipe Schedule 26, 10"	Lf	490.00	\$ 215.68	\$ 105,683.20	
8.0000	810.0112	Storm Sewer Pipe Schedule 26, 12"	Lf	84.00	\$ 89.84	\$ 7,546.56	
9.0000	811.0115	Sanitary Sewer Wyes, (Various)	Ea	7.00	\$ 767.12	\$ 5,369.84	
10.0000	100.4000	48" Sanitary Sewer Manholes	Ea	3.00	\$ 11,510.00	\$ 34,530.00	
11.0000	205.0100	Excavation Road Down 5'	Cy	1,018.52	\$ 8.79	\$ 8,952.79	
12.0000	830.0148	Storm Sewer HDPE, 48"	Lf	220.00	\$ 96.37	\$ 21,201.40	
13.0000	608.0348	Storm Sewer Pipe Reinforced Concrete Class III, 48"	Lf	220.00	\$ 141.29	\$ -	
14.0000	830.0142	Storm Sewer HDPE, 42"	Lf	60.00	\$ 86.64	\$ 5,198.40	
15.0000	608.0342	Storm Sewer Pipe Reinforced Concrete Class III, 42"	Lf	60.00	\$ 108.58	\$ -	
16.0000	100.3500	2x3 Inlets	Ea	1.00	\$ 4,562.63	\$ 4,562.63	
17.0000	100.3500	72" Storm Sewer Manhole	Ea	3.00	\$ 5,587.13	\$ 16,761.39	
Total Bid Price						\$ 255,472.56	

Exclusions/Clarifications/Notes

- Bonds and Permits are excluded.
- Traffic Control is excluded.
- Utility disconnects if any (gas, electrical, cable, fiber, etc.) are excluded.
- A locate request thru Diggers Hotline will be submitted. However, private lines (gas, electrical, cable, fiber, etc.) are to located by others. If not Gerke Excavating is not responsible if damaged.
- EBS is not included for soft spots if sub-grade does not meet requirements.
- Pavement Removal is Excluded
- Existing soils shall be used for onsite grading. No import of granular fill or aggregate base is included.
- No staking is included
- Not responsible for thawing or snow removal for winter conditions.
- Bacteria and pressure testing for our water and sewer mains only. No compaction or any other form of testing is included.
- Asphalt, concrete and patch work is excluded.
- Any landscaping items (seeding, fertilizer, mulch, sod, mulch, bushes, plants, trees, etc.) are excluded.
- Erosion control blanket is excluded.
- Insulation or vapor barrier is excluded.
- Any transitions or accessory item (downspout tie-in, etc.) tying to our utility work is excluded.
- Removal of polluted or hazardous soils, if found, is excluded.
- Repair of any cracking to existing foundations or adjacent structures due to heavy equipment being used is excluded.
- Any repair or restoration to remaining building(s) is excluded.
- Tolerance of grades will be within +/- .1' of proposed grades.
- All items are tied without discussion.

Sincerely,

 Eric Stickney
 Gerke Excavating