



No.	Description	Date

Graphic Scale: VARIES

Last Update: 11.1.2023

A200.1

- ELEVATION KEY NOTES:**
NOTE: NOT ALL NOTES APPLY TO EACH SHEET.
- TUCKPOINT.
 - NEW CLAD WOOD WINDOWS w/ ALUM PANNING.
 - RESTORE HISTORIC WINDOWS.
 - RESTORE FRAME. NEW WOOD SASH.
 - RESTORE LIMESTONE.
 - NEW WOOD STOREFRONT w/ WOOD BULKHEADS.
 - NEW METAL CORNICE / GUTTER w/ BRACKETS.
 - NOT USED.
 - FIX CRACK - SEE STRUCTURAL.
 - NEW SIGN BOARD BY OWNER.
 - NOT USED.
 - NEW METAL HIP CAP.
 - NEW METAL CORNICE.
 - NEW METAL MANSARD ROOF.
 - REPLACE DAMAGED BRICK IN KIND.
 - NEW STEEL COLUMN.
 - RESTORE WOOD WINDOW / TRANSOM.
 - NEW WOOD DOOR & FRAME.
 - REPAIR CORBELLED MASONRY CORNICE. (MOULDED BRICK).
INSTALL METAL FLASHING OVER TOP OF LIMESTONE TOP COURSE.
 - RESTORE METAL CORNICE. FILL RUSTED HOLES w/ BONDO. TREAT RUST w/ RUST CONVERTER. (PAINT).
 - RECONFIGURE SLOPED APPROACH TO ENTRY DOOR. VERIFY EXACT CONFIGURATION DURING EXPLORATION STAGE & REPORT TO ARCHITECT.
 - EXISTING IRON COLUMN. (CLEAN, PRIME & PAINT)
 - NOT USED.
 - RESET LOOSE TERRA COTTA. VERIFY ANCHOR CONDITION & REPORT TO ARCHITECT.
 - INSPECT STUCCO. REPLACE IN KIND WHERE DAMAGED OR DELAMINATED.
 - NOT USED.
 - REMOVE STUCCO. REPOINT MORTAR JOINTS IN BRICK WALL.
 - NEW EPDM ROOF SYSTEM - SEE ROOF PLAN.
 - NEW 4" FACE BRICK VENEER. 2 1/2" X 7 1/2" X 3 1/2"
 - NEW METAL CLAD WOOD WINDOW.
 - NEW PRE-FINISHED METAL WALL CAP.
 - SALVAGED LIMESTONE LUG SILL FROM CONTRACTORS' STOCK.
 - NEW THERMALLY BROKEN ALUMINUM WINDOW.
 - 8"x8" BRICK/LIMESTONE CHECKERBOARD PATTERN.
 - RESTORE & PAINT HISTORIC METAL PANEL. FILL RUSTED HOLES w/ BONDO. TREAT RUST w/ RUST CONVERTER. (PAINT).
 - NEW GUTTER & DOWNSPOUT.
 - REPLICATE MISSING PORTION OF WOOD MULLION. (PAINT)
 - NOT USED.
 - METAL FRONT & CAPS ON DORMERS.
 - SPECIAL MOULDED BRICK. (EXISTING) SEE 10A500.
 - 1/2 CLAD DORIC COLUMN.
 - 42" HIGH GUARD RAILING.
 - BUILD NEW WALL / PARAPET ON TOP OF EXISTING WALL TO FACILITATE NEW SLOPING ROOF AT ROOF TOP PATIO 322. (SEE ROOF PLAN)
 - INFILL FORMER DOOR OPENING BELOW NEW WINDOW.

- ELEVATION GENERAL NOTES:**
- VERIFY SIZE AND LOCATIONS OF ALL MECH. OPENINGS. GENERAL CONTRACTOR TO SEAL LOUVER PERIMETER AND PAINT - TYPICAL.
 - GENERAL CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS PRIOR TO BEGINNING WORK AND SHALL NOTIFY THE ARCHITECT OF DISCREPANCIES BETWEEN ACTUAL AND CALLED DIMENSIONS.
 - G.C. TO PROVIDE CONC EQUIPMENT PADS/CURBS AS REQUIRED FOR MECH/ELECTRICAL EQUIP. VERIFY SIZE/PROFILE/LOCATION w/ MECH/ELEC.
 - G.C. SHALL INSTALL COMPRESSIBLE FILLER AT ALL MASONRY WALL CONTROL/EXPANSION JOINTS AND SEAL BOTH SIDES. WALL REINF. TO DISCONTINUE AT JOINTS, TYP.
 - ALL EXTERIOR WALLS SHALL HAVE A 2 HOUR FIRE RATING.
 - REMOVE ALL PAINT - CLEAN MASONRY.
 - REMOVE ALL VEGETATIVE GROWTH, MISC ANCHORS, BOLTS, FASTENERS, SIGN REMNANTS - PATCH MASONRY.

MATERIAL LEGEND:

Symbol	Material	BRICK SIZE, (INCHES)
[Pattern]	BRICK	ODDFELLOWS 2 1/2" x 8" x 4"
[Pattern]	MENDRALSKI	2 1/2" x 7 1/2" x 4"
[Pattern]	REUTER-MADER	2 1/2" x 7 1/2" x 3 1/2"
[Pattern]	LIMESTONE	
[Pattern]	TERRA COTTA	
[Pattern]	SLATE	
[Pattern]	STUCCO	
[Pattern]	METAL	



1 WEST ELEVATION
1/4" = 1'-0"