


P.O. BOX 961089
FORT WORTH, TEXAS 76161
(1616 RUBLEE ST)
17-10286-10

SAWCUT AND REMOVE BITUMINOUS PAVEMENT AS DIRECTED BY CITY ENGINEER (TYP)

SAWCUT AND REMOVE BITUMINOUS PAVEMENT AS DIRECTED BY CITY ENGINEER (TYP)

REMOVE DRIVE OPENING DO NOT REPLACE

20' TRANSITION NEW CURB ALIGNMENT TO MATCH EXISTING CURB



QUANTITIES

- 1523 SQ. FT. 5" CONCRETE SIDEWALK
- 600 SQ. FT. 7" CONCRETE PAVEMENT INCL. DRIVE APPROACHES
- 1300 L.F. L.F. STANDARD CURB & GUTTER INCL. 6" COMPACTED CR. ROCK
- 3 EA. DETECTABLE WARNINGFIELD
- 230 SQ. YDS. 3" HOX MIX BITUMINOUS PAVEMENT
- 2630 SQ. YDS. 5" HOT-MIX BITUMINOUS PAVEMENT
- 2650 SQ. FT. 4" BLACK DIRT, SEED, FERTILIZER & MULCH
- 1 L.S. EROSION CONTROL
- 1 L.S. TRAFFIC CONTROL

REMOVALS

- 99 L.F. CONC. SAWING
- 1364 L.F. BITUMINOUS SAWING
- 64 SQ. FT. CONCRETE (ANY THICKNESS)
- 3630 SQ. FT. BITUMINOUS PAVEMENT (ANY THICKNESS)
- 1386 L.F. CURB & GUTTER
- 1 L.S. EXCESS MATERIAL REMOVAL AND DISPOSAL

NOTE

CONTRACTOR IS TO VERIFY LOCATION OF ALL UTILITIES PRIOR TO ANY CONSTRUCTION

CONTRACTOR SHALL INSTALL INLET PROTECTION PER CITY DETAIL IN ALL INLETS

CONTRACTOR SHALL FIELD VERIFY ALL CATCH BASIN AND MANHOLE INVERT ELEVATIONS. ANY DISCREPANCY FOUND BETWEEN FIELD AND PLAN CONDITIONS SHOULD BE BROUGHT TO THE ATTENTION OF THE PROJECT ENGINEER OR CITY REPRESENTATIVE PRIOR TO INSTALLATION

CONTRACTOR IS RESPONSIBLE FOR ADJUSTING ALL MANHOLES AND CATCH BASINS WITH NEW CONC. ADJUSTING RINGS.
CITY WILL PROVIDE ALL CASTINGS

KWIK TRIP INC.
1626 OAK ST
LA CROSSE, WI 54603
17-10285-80

CITY WATER UTILITY TO REMOVE AND RELOCATE THE HYDRANT AND CONTROL VALVE

CONTRACTOR SHALL MAINTAIN PROPER PROTECTION AND ACCESS TO HYDRANT THROUGHOUT ENTIRE PROJECT DURATION

CATCH BASIN #7
INSTALL NEW
STA. 5+98
FL. 644.91

REMOVE BITUMINOUS PAVEMENT AS DIRECTED BY CITY ENGINEER (TYP)

CATCH BASIN #6
INSTALL NEW
STA. 2+87
FL. 643.90
INV. W 640.87

INSTALL 6' X 7" CONCRETE SIDEWALK THROUGH DRIVE SECTION AND 7" DRIVE APPROACH

INSTALL 6' X 5" CONCRETE SIDEWALK


BOULEVARD TO BE RESTORED WITH 4" TOPSOIL, SEED, FERTILIZER AND MULCH

SAWCUT AND REMOVE BITUMINOUS PAVEMENT AS DIRECTED BY CITY ENGINEER (TYP)

REMOVE CATCH BASIN

OAK ST
OAK ST

OAK ST & GILLE
53' NORTH
94' NORTH
96' NORTH
136' NORTH
500' NORTH
574' NORTH (S.



645	EDF # 16-C
644	PROJECT No.
643	LOCATION