



RIGHT OF
WAY VARIES

CONSTRUCTION NOTE:
**POTHOLE WHERE
NECESSARY AND ADJUST
DEPTH ACCORDINGLY**

THE UTILITIES SHOWN ON THIS PLAN ARE
INDICATED IN ACCORDANCE WITH AVAILABLE
RECORDS. THE CONTRACTOR SHALL BE
RESPONSIBLE FOR OBTAINING EXACT
LOCATIONS AND ELEVATIONS OF ALL UTILITIES
FROM THE OWNERS OF THE RESPECTIVE
UTILITIES AND FROM FIELD VERIFICATION.

CONSTRUCTION NOTE:
**BURY CABLE AT A MINIMUM OF 36" DEPTH
UNLESS OTHERWISE NOTED ON PRINTS.**

CONSTRUCTION NOTE:
**CHARTER COMMUNICATIONS WILL PLACE
PROPOSED CABLE'S IN CORRIDOR AS CLOSE TO
THE BACK OF RIGHT-OF-WAY AS POSSIBLE,
PENDING LOCATES.**

TB : TREE BORE(DIRECTIONAL BORE)
RB : ROAD BORE (DIRECTIONAL BORE)
T : TRENCH
HD : HAND DIG
P : PLOW
R&P : ROD AND PULL THROUGH EXISTING 2" CONDUIT

**CHARTER COMMUNICATIONS PROPOSES
TO BURY (1) COAX COMMUNICATION
CABLE IN A 2" CONDUIT**

--- =
CABLES

PROPOSED
CABLES

LEGEND

⊗

JOINT POLE

⊗

NEW JOINT POLE

×

POWER POLE

×

NEW POWER POLE

○

TELEPHONE POLE

○

NEW TELEPHONE POLE

⊠

EXISTING PEDESTAL

⊠

NEW PEDESTAL

⋈

ANCHOR

⋈

NEW ANCHOR

⋈

JOINT ANCHOR

⋈

NEW JOINT ANCHOR

⋈

FOREIGN ANCHOR

⋈

DOWNGUY

⋈

NEW DOWNGUY

⋈

UTILITY VALVE

○

MANHOLE

○

EXISTING FIBER COIL

○

NEW FIBER COIL

○

EXISTING HAND HOLE

○

NEW HAND HOLE

○

SHRUBS

○

DECIDUOUS TREE

⋈

GROUND

⋈

NEW GROUND

⋈

PROPERTY LINE

⋈

ROADWAY CENTERLINE

⋈

FIBER WARNING SIGN

⋈

TRAFFIC LIGHT

⋈

HYDRANT

⋈

SIGNS

⋈

STREET LIGHT

⋈

CONIFEROUS TREE

PROPOSED
FIBER
STRAND

GAS

WATER

ELECTRICAL

STORM

SANITARY

CABLE TV

TELEPHONE

PROJECT #2580711

PERMIT ID#2580711CITY

Charter

COMMUNICATIONS

N

↑

ADDRESS

2600 QUARRY RD

FIELD BY:

DATE:

DRAFTED BY:

KIS

DATE:

4/20/2021

DESIGNED BY:

DATE:

ASBULTS BY:

DATE:

LOCATION

LA CROSSE, WI

1