



SITE NOTES

- The location of existing utilities, both underground and overhead are approximate only and have not been independently verified by the owner or its representatives. The contractor shall be responsible for determining the exact location of all existing utilities, whether shown on these plans or not, before commencing work, and shall be fully responsible for any and all damages which might be caused by the contractor's failure to exactly locate and preserve any and all utilities.
CALL DIGGERS HOTLINE (800) 242-8511
- The underground locations of the Public Utilities were marked by representatives of those companies. The locations of the privately owned underground utilities were not marked.
- There may be more underground utility installations within the project area that are not shown.
- It shall be the contractors responsibility to arrange for any necessary inspections by local government that may be required.
- Any and all parties utilizing vertical datum shall always check into at least two (2) benchmarks to avoid mistakes due to hydrant adjustments or transpositional errors. Failure to do so will be considered tantamount to gross negligence and subject the offending party to any damages resulting therefrom.

NOTES - DEMOLITION PLAN

- ① REMOVE EXISTING PAVEMENT
- ② SAW CUT EXISTING ASPHALT
- ③ REMOVE EXISTING WALL
- ④ REMOVE EXISTING CURB AND GUTTER
- ⑤ REMOVE EXISTING LANDSCAPING
- ⑥ COORDINATE WITH UTILITY COMPANY TO RELOCATE GAS LINE
- ⑦ PROTECT EXISTING UTILITY
- ⑧ PROTECT EXISTING UNDERGROUND STORAGE TANKS

REVISIONS	BY

PARAGON ASSOCIATES
 Environmental Design & Consulting
 CIVIL ENGINEERING · LANDSCAPE ARCHITECTURE · SURVEYING
 632 COPELAND AVENUE · LA CROSSE, WI 54603
 Tel: 608.781.3110 Fax: 608.781.3197 Paragon-Assoc.biz

PREPARED FOR:
XXXX

**ADVANCED FIBER PRODUCTS - ADDITION
 2970 LUOYANG AVENUE
 LA CROSSE, WISCONSIN
 DEMOLITION PLAN**

DRAWN	C.G.
PROJECT No	15-086
DATE	09/18/2015
SCALE	1"=20'
CAD FILE	15-086 Advanced Fiber Add 02
SHEET	

C1

