



PREPARED FOR:  
 Buswell Bridgeview Plaza Building 1

**BUSWELL BRIDGEVIEW PLAZA**  
 ROSE STREET  
 LA CROSSE, WISCONSIN 54603  
 PUBLIC UTILITIES

DRAWN	C.G.
PROJECT No	26-016
DATE	05/28/2026
SCALE	1"=20'
CAD FILE	26-016 Bridgeview05.DWG
SHEET	

**C401**

**PHASE 2 BUILDING**

PROVIDE NEW 8" SAN SERVICE AND 6" DIP WATER SERVICES. PROVIDE CONNECTIONS PER CITY REQUIREMENTS.

**MH #2**  
 RIM = 645.85  
 INV NE = 635.03  
 INV SE = 634.93  
 INV SW = 635.91  
 D = 10.92

**MH #3**  
 RIM = 645.95  
 INV NE = 637.24  
 INV SE = 637.34  
 D = 8.71

NEW FIRE HYDRANT ASSEMBLY

333 LF 10" SDR 35 PVC SANITARY SEWER s=0.40% (1.33')

335LF 8" CLDIP WATER MAIN

**ENTERPRISE**

**HARBOR FREIGHT**

**PHASE 1 BUILDING**

PROVIDE NEW 4" SDR 35 PVC SANITARY SEWER SERVICE FROM NEW MAIN TO EXISTING LINE. CUT, COUPLE AND CONNECT AS REQUIRED.

**MH #4**  
 RIM = 646.60  
 INV NW = 637.93  
 D = 8.67

PROVIDE NEW 3" TYPE COPPER WATER SERVICE and 6" DIP CONNECTIONS FOR HARBOR FREIGHT. PROVIDE CORP COCK AND CURB STOP PER CITY REQUIREMENTS.

PROVIDE NEW 8" SAN SERVICE AND 6" DIP WATER SERVICES. PROVIDE CONNECTIONS PER CITY REQUIREMENTS.

**MH #1**  
 RIM = 645.85  
 INV NE = 632.70  
 INV SW = 633.80  
 D = 13.15

CUT, COUPLE, AND CONNECT TO EXISTING 6" WATER MAIN. PROVIDE NEW 8 TO 6 REDUCER.

NEW FIRE HYDRANT ASSEMBLY

SAN SVPR AND WTR EASEMENT - 30FT TYP

432 LF 8" CLDIP WATER MAIN

283 LF 10" SDR 35 PVC SANITARY SEWER s=0.40% (1.13')

465 LF 8" CLDIP WATER MAIN

STORM INLET  
 RIM = 644.01  
 INV. NW (in) = 639.31  
 INV. NE (in) = 636.36  
 INV. E (in) = 636.25  
 INV. W (out) = 636.10

EXISTING MH  
 CORE EXISTING  
 INV NW = 629.80

STORM INLET  
 RIM = 640.00  
 INV. NE (in) = 637.72  
 INV. SW (out) = 627.77

80 LF 10" SDR 35 PVC SANITARY SEWER s=2.22% (2.90')

497 LF, 30" @ 1.00%  
 497 LF, 30" @ 0.10%

LIBERTY ST



