



**MUNICIPAL**  
**WELL & PUMP**  
A Division of Midwest Well Services, Inc.

July 2, 2020

City of La Crosse  
Attn: Lee Anderson  
400 La Crosse Street  
La Crosse, WI 54601

**RE: Well No. 20 Investigation**

Dear Lee,

As we discussed, there is likely a hole in the screen or the casing. As you are aware, the pump needs to be removed to fully video the well; however, you had mentioned that you would like to dynamically video log the well to perhaps get an idea where the gravel pack is coming in during pumping operations. This is certainly something that can be done prior to removal of the pump.

Please review the following scopes of work and the associated cost for the initial phase of the project:

1. Load and mobilize to job site.
2. Set up rig and disconnect the pump from the main.
3. Lift pump and set on blocks to allow room for the camera.
4. Set up discharge to run to waste.
5. Run pump to waste and video log the well to see where the gravel pack is entering well.
6. Remove the pump from the well.
7. Video log entire well casing and screen.
8. Demobilize from job site.
9. Provide recommendations to the City for repairs.

.....**Lump Sum: \$ 7,247**

We trust you will find this correspondence to your understanding. Should you have any questions or concerns regarding this proposal, or if there is any other way we can be of assistance to your community, please contact our offices at your earliest convenience. We appreciate this opportunity to provide you with this proposal and look forward to the opportunity to provide the City of La Crosse expert service on this project.

Sincerely,  
MUNICIPAL WELL & PUMP

Marty Van Ells  
Project Manager

C:\Users\marty van ells\Desktop\Proposals\Marty's Proposals 2020\La Crosse #20 Investigation\_7-2-20\La Crosse Well 20 Investigation\_7-2-20.doc