



Restaurant Support Office
6800 Bishop Road, Plano, TX 75024
Tele: 972-769-3100 Fax: 972-769-3101

Restaurant:

Raising Cane's
Restaurant #C1148
Hwy 16 & Braund St
La Crosse, WI 54560
P4-V-AV (A)

Designer's Information:

SHREMSHOCK
Shremshock Architects, Inc.

7775 Walton Parkway Suite 250 New Albany, OH 43054
t: 614 545-4550 | f: 614 545-4555 | shremshock.com
Gerald S. Shremshock, Architect
Timothy J. Shremshock, Architect

Prototype Phase: 2023

Project Issue Date: 00-00-0000

SAI Project Manager: PDS

100% SUBMISSION
03-11-2024



Sheet Versions:

#	Date	Description
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-
-	-	-

Sheet Title:

ROOF PLAN

Sheet Number:

A1.50

SAI Job Number: 230372

GENERAL NOTES	
1	THE DETAILS SHOWN ON THE DRAWINGS ARE TO BE CONSIDERED SCHEMATIC. ITEMS SUCH AS PARAPET FLASHING, CANTS, BLOCKING, ROOF PENETRATIONS AND EXPANSION JOINTS ARE TO BE INSTALLED PER MANUFACTURERS STANDARD ROOF DETAILS PRIOR TO THE BEGINNING OF THE WORK.
2	REFER TO TRUSS COORDINATION PLAN FOR DECK BEARING ELEVATION@ ROOF.
3	REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR ADDITIONAL ITEMS ON OR THROUGH ROOF.
4	CLEAN ROOF OF ALL CONSTRUCTION DEBRIS AT PROJECT COMPLETION.
5	ALL ROOF TOP MECHANICAL EQUIPMENT SHALL BE STRAPPED AND SECURED TO THE ROOF PER EQUIPMENT MANUFACTURER STANDARDS.
6	CONTRACTOR TO VERIFY WEIGHT AND LOADING REQUIREMENTS OF ALL ROOF TOP EQUIPMENT WITH DATA SHEETS PRIOR TO TRUSS DESIGN.
7	IN ADDITION, VERIFY WEIGHT AND LOADING OF WOOD MILLWORK ITEMS SUSPENDED FROM BOTTOM CHORD IN DINING ROOM.
8	GENERAL CONTRACTOR TO VERIFY REQUIREMENTS OF ALL ROOFTOP EQUIPMENT WITH SPECIFICATION SHEETS PRIOR TO TRUSS DESIGN.
9	GENERAL CONTRACTOR TO COORDINATE FREEZER EQUIPMENT PER MANUFACTURER SPECIFICATIONS.
ROOF TOP EQUIPMENT AND ACCESSORIES	
1	RTU-1. PROVIDE TAPERED INSULATION CRICKET AT CURB.
2	RTU-2. PROVIDE TAPERED INSULATION CRICKET AT CURB.
3	MAKE-UP AIR UNIT. PROVIDE TAPERED INSULATION CRICKET AT CURB.
4	HOOD EXHAUST FAN. PROVIDE TAPERED INSULATION CRICKET AT CURB.
5	ICE MACHINE CONDENSER. RE: 7/A&21
6	COOLER / FREEZER CONDENSER. RE: 7/A&21
7	RESTROOM EXHAUST FAN
8	AWNING BY VENDOR.
9	PRIMARY ROOF SCUPPER - COORDINATE w/ A0.10 FOR SITEDRAINAGE. RE: 5/A&40
10	SECONDARY OVERFLOW SCUPPER
13	ROOF ACCESS HATCH
14	GUARD RAIL. RE: STRUCTURAL DETAIL 23/SD2.2
15	ROOF WALKWAY PADS.
17	ROOF PENETRATION FOR CONDENSER UNIT
21	GAS WH EXHAUST
23	PLUMBING STACK VENT
24	ROOF HYDRANT RE: PLUMB
25	ROOF PENETRATION FOR IT EQUIPMENT
26	EXPO CANOPY. SEE SHEET A0.23.

