RIVER POINT K1 SITE

FINAL DESIGN REVIEW

ISG PROJECT # 23-30331

LEGEND

LA CROSSE, WISCONSIN

EXISTING	
	CITY LIMITS
	SECTION LINE
	QUARTER SECTION LINE
	RIGHT OF WAY LINE
	PROPERTY / LOTLINE
	EASEMENT LINE
ΔΔ	ACCESS CONTROL
	WATER EDGE
— — WET — — —	WETLAND BOUNDARY
<u> 4117 </u>	WETLAND / MARSH
xxxx	FENCE LINE
>>><	CULVERT
	STORM SEWER
	SANITARY SEWER
	SANITARY SEWER FORCEMAIN
	WATER
——————————————————————————————————————	GAS
——————————————————————————————————————	OVERHEAD ELECTRIC
UE	UNDERGROUND ELECTRIC
UT	UNDERGROUND TELEPHONE
$-\!\!\!-\!\!\!-\!\!\!-\!\!\!\!-\!\!\!\!-\!\!\!\!-\!\!\!\!\!-\!\!\!\!\!-\!\!\!\!$	UNDERGROUND TV
	OVERHEAD UTILITY
$-\!\!\!-\!\!\!-\!\!\!-\!\!\!-\!\!\!-\!\!\!\!-\!\!\!\!-\!\!\!\!-\!$	UNDERGROUND UTILITY
——————————————————————————————————————	UNDERGROUND FIBER OPTIC
<u> </u>	CONTOUR (MAJOR)
— — <u> </u>	CONTOUR (MINOR)
<pre>{·}</pre>	DECIDUOUS TREE
	CONIFEROUS TREE
	TREE LINE
\bigcirc	MANHOLE/STRUCTURE
	CATCH BASIN
- 	HYDRANT
\bowtie	VALVE
\otimes	CURB STOP
Ø	POWER POLE
	UTILITY PEDESTAL / CABINET

PROPOSED LOT LINE STORM SEWER

SANITARY SEWER (PIPE WIDTH) **UNDERGROUND TV** CONTOUR MANHOLE (STORM, SANITARY) CATCH BASIN **HYDRANT**

VALVE



ABBREVIATIONS:

AFF ABOVE FINISHED FLOOR CMP CORRUGATED METAL PIPE AGG AGGREGATE APPROX APPROXIMATE CONC CONCRETE ARCH ARCHITECT, ARCHITECTURAL CONST CONSTRUCTION BASEMENT FLOOR ELEVATION CONT CONTINUOUS BENCHMARK CURB AND GUTTER CAD COMPUTER-AIDED DESIGN DIMENSION EACH CIP CAST IRON PIPE ELEC ELECTRICAL

CIPC CAST IN PLACE CONCRETE EQUAL **EXISTING**

GALV GALVANIZED GENERAL CONTRACTOR

GPM GALLONS PER MINUTE J-BOX JUNCTION BOX GATE VALVE JOINT LINEAR FEET FIRE DEPARTMENT CONNECTION HDPE HIGH DENSITY POLYETHYLENE HORIZ HOUR HIGH WATER LEVEL MINIMUM INCH MISC MISCELLANEOUS INV NO NUMBER

OCEW ON CENTER EACH WAY OHD OVERHEAD DOOR PED PEDESTAL, PEDESTRIAN LOWEST STRUCTURAL OPENING PROPERTY LINI POLYPROPYLENE PVC POLYVINYL CHLORIDE PVMT PAVEMENT QTY QUANTITY

OC ON CENTER

REM REMOVE ROW RIGHT OF WAY POUNDS PER SQUARE INCH T/C TOP OF CURB

RCP

T/W TOP OF WALL R/W RIGHT OF WAY TYP UTILITY, UNDERGROUND TELEPHONE SCHEDULE VITRIFIED CLAY PIPE SQUARE FOOT W/O SPEC SPECIFICATION YD STATION YEAR SQUARE YARD

REINFORCED CONCRETE PIPE

ROOF DRAIN

REBAR REINFORCING BAR

WITHOUT WITH YARD

TEMP TEMPORARY

TRANS TRANSFORMER

TELEVISION

TNFH TOP NUT OF FIRE HYDRANT

THRU THROUGH

SHEET INDEX

C0-10 TITLE SHEET C0-20 SITE DETAILS C0-21 SITE DETAILS C0-22 SITE DETAILS C0-23 SITE DETAILS C0-24 SITE DETAILS

C0-25 SITE DETAILS

C1-20 EROSION CONTROL DETAILS C1-40 EROSION CONTROL PLAN

C2-10 EXISTING SITE AND REMOVAL PLAN

C3-10 SITE PLAN C3-20 SITE UTILITY PLAN C4-10 GRADING PLAN

C5-40 FURNISHINGS PLAN

E2-00 PHOTOMETRIC PLAN E2-01 SITE ELECTRICAL FIXTURES

PROJECT GENERAL NOTES

1. ALL WORK SHALL CONFORM TO THE CONTRACT DOCUMENTS, WHICH INCLUDE, BUT ARE NOT LIMITED TO. THE OWNER - CONTRACTOR AGREEMENT, THE PROJECT MANUAL (WHICH INCLUDES GENERAL SUPPLEMENTARY CONDITIONS AND SPECIFICATIONS), DRAWINGS OF ALL DISCIPLINES AND ALL ADDENDA, MODIFICATIONS, AND CLARIFICATIONS ISSUED BY ARCHITECT/ENGINEER.

CONTRACT DOCUMENTS SHALL BE ISSUED TO ALL SUBCONTRACTORS BY THE GENERAL CONTRACTOR IN COMPLETE SETS IN ORDER TO ACHIEVE THE FULL EXTENT AND COMPLETE COORDINATION OF ALL WORK.

WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED 9. THE CONTRACTOR IS TO CONTACT "DIGGERS HOTLINE" DIMENSIONS. NOTIFY ARCHITECT/ENGINEER OF ANY DISCREPANCIES OR CONDITIONS REQUIRING INFORMATION OR CLARIFICATION BEFORE PROCEEDING WITH THE WORK.

4. FIELD VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS NOTIFY ARCHITECT/ENGINEER OF ANY DISCREPANCIES OR CONDITIONS REQUIRING INFORMATION OR CLARIFICATION BEFORE PROCEEDING WITH THE WORK.

5. DETAILS SHOWN ARE INTENDED TO BE INDICATIVE OF THE PROFILES AND TYPE OF DETAILING REQUIRED THROUGHOUT THE WORK. DETAILS NOT SHOWN ARE SIMILAR IN CHARACTER TO DETAILS SHOWN. WHERE SPECIFIC DIMENSIONS, DETAILS, OR DESIGN INTENT CANNOT BE DETERMINED, NOTIFY ARCHITECT/ENGINEER BEFORE PROCEEDING WITH THE WORK.

6. ALL MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT SHALL BE APPLIED, INSTALLED, CONNECTED, ERECTED, CLEANED, AND CONDITIONED ACCORDING TO MANUFACTURERS' INSTRUCTIONS. IN CASE OF DISCREPANCIES BETWEEN MANUFACTURERS' INSTRUCTIONS AND THE CONTRACT DOCUMENTS, NOTIFY ARCHITECT/ENGINEER BEFORE PROCEEDING WITH THE

INC. AND MAY NOT BE USED, COPIED OR DUPLICATED

WITHOUT PRIOR WRITTEN CONSENT **PROJECT** 7. ALL DISSIMILAR METALS SHALL BE EFFECTIVELY ISOLATED

SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

RIVER POINT

K1 SITE

WISCONSIN

LA CROSSE

FILE NAME

DRAWN BY

TITLE

DESIGNED BY

REVIEWED BY

CLIENT PROJECT NO.

REVISION SCHEDULE DESCRIPTION 23-30331 PROJECT NO.

BDC

KBR

ORIGINAL ISSUE DATE 03/28/2024

BDC/SMW

30331-C0-GENERAL

PROJECT INDEX:

OWNER:

WAR EAGLE, LLC **1310 WEST WISCONSIN STREET SPARTA, WI 54656**

PROJECT ADDRESS / LOCATION:

LOT 10 OF RIVER POINT DISTRICT II S31 TWP16N R07W

IPS

LA CROSSE, WISCONSIN

MANAGING OFFICE:

TEL TELEPHONE

LA CROSSE OFFICE **201 MAIN STREET SUITE 1020** LA CROSSE, WI 54601 PHONE: 608.789.2034

PROJECT MANAGER: KRIS ROPPE EMAIL: kris.roppe@isginc.com

SPECIFICATIONS REFERENCE

ALL CONSTRUCTION SHALL COMPLY WITH THE CITY OF LA CROSSE STANDARD SPECIFICATIONS, CURRENT EDITION, WISDOT STANDARD SPECIFICATIONS, 2024 EDITION, WISDOT CONSTRUCTION AND MATERIALS MANUAL, CURRENT EDITION, WISCONSIN DEPARTMENT OF SAFETY AND PROFESSIONAL SERVICES STATE PLUMBING CODE, CURRENT EDITION, AND STANDARD SPECIFICATION FOR SEWER & WATER CONSTRUCTION IN WISCONSIN, 6th EDITION, UNLESS DIRECTED OTHERWISE.

HORIZONTAL COORDINATES HAVE BEEN REFERENCED TO THE NORTH AMERICAN DATUM OF 1983 (NAD83), 2011 ADJUSTMENT (NAD83(2011)) ON THE LA CROSSE COUNTY COORDINATE SYSTEM, IN U.S. SURVEY FEET.

B.M. ELEVATION = 645.50°

FROM EACH OTHER TO AVOID GALVANIC CORROSION.

OF THE KNOWLEDGE OF I & S GROUP, INC. (ISG). NO

ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.

ANY DISCREPANCIES OR VARIATIONS FROM PLAN.

PRIOR TO ANY EXCAVATION / CONSTRUCTION (811 OR

www.DiggersHotline.com

SHOWN ON THE PLANS ARE FOR GENERAL INFORMATION

ONLY AND ARE ACCURATE AND COMPLETE TO THE BEST

WARRANTY OR GUARANTEE IS IMPLIED. THE CONTRACTOR SHALL VERIFY THE SIZES, LOCATIONS, AND ELEVATIONS OF

CONTRACTOR SHALL IMMEDIATELY NOTIFY ENGINEER OF

FOR UTILITY LOCATIONS A MINIMUM OF 3 BUSINESS DAYS

8. THE LOCATION AND TYPE OF ALL EXISTING UTILITIES


TOP NUT OF FIRE HYDRANT

TOPOGRAPHIC SURVEY


THIS PROJECT'S TOPOGRAPHIC SURVEY CONSISTS OF DATA COLLECTED IN JANUARY 2024 BY ISG.

TITLE SHEET

SHEET **CO-10**




RESIDENTIAL SANITARY SERVICE NTS




NOTES: 1. GRANULAR BEDDING AND ENCASEMENT FOR SANITARY SEWER PIPES SHALL BE INCIDENTAL TO CONSTRUCTION

PIPE BEDDING SANITARY SEWER



TYPICAL WATER SERVICE NTS WM500



NOTE:

1. GRANULAR BEDDING AND ENCASEMENT FOR WATERMAIN PIPES SHALL BE INCIDENTAL TO CONSTRUCTION

> PIPE BEDDING WATERMAIN NTS

4" 3 INCH CLEAN STONE —

ROCK LANDSCAPING WITH UNDERDRAIN DETAIL


/— ADJACENT WALK

GEOTEXTILE FABRIC TYPE DF —

8" BASE AGGREGATE OPEN GRADED 🔊

PIPE UNDERDRAIN WRAP

SEE SCHEDULE FOR PIPE SIZE



SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

FOR

PRELIMINARY

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

F		ER PO			CONSTRUC
LA CRO	SSE		WISCO	NSIN	O
	RE	EVISION SCHEDU			()
DATE		DESCRIPTION	N .	BY	
					~
					OR
					U
PROJECT	NO.	23-30331			
FILE NAM		30331-C0-DI			0

ROJECT NO.	23-30331	
LE NAME	30331-C0-DETAILS	
RAWN BY	BDC	
ESIGNED BY	BDC/SMW	
EVIEWED BY	KBR	
RIGINAL ISSUE DATE	03/28/2024	


TITLE

CLIENT PROJECT NO.

SITE DETAILS

CO-20

PR |




TRENCH WIDTH				
PIPE Ø	TRENCH WIDTH			
36" OR LESS	D _O + 24"			
42" TO 54"	1.5 x D _O			
60" OR OVER	D _O + 36"			

NOTES:

1. GRANULAR BEDDING AND BACKFILL FOR STORM DRAIN PIPES SHALL BE INCIDENTAL TO STORM DRAIN CONSTRUCTION

NON-CONCRETE STORM DRAIN PIPE BEDDING



TRENCH WIDTH					
PIPE Ø	TRENCH WIDTH				
36" OR LESS	D _O + 24"				
42" TO 54"	1.5 x D _O				
60" OR OVER	D _O + 36"				

NOTES:

1. GRANULAR BEDDING AND BACKFILL FOR STORM DRAIN PIPES SHALL BE INCIDENTAL TO STORM DRAIN CONSTRUCTION

REINFORCED CONCRETE STORM DRAIN PIPE BEDDING

SEE STORM DRAIN SCHEDULE -UNIFORMLY COMPACTED CRUSHED STONE OR GRANULAR BEDDING PER MANUFACTURER'S RECOMMENDATION

KEY NOTES:

FRAME AND COVER-

RIM ELEVATION—

(SEE STORM DRAIN SCHEDULE)


(SEE STORM DRAIN SCHEDULE)


TOP SOIL —

DESIGN SHOULD ACCOUNT FOR ROOT DEPTH TO ALLOW TURF TO GROW AND

6" MIN ON 8" - 24" DRAIN BASIN, 10" MIN ON 30" DRAIN BASIN. VERIFY WITH MANUFACTURER'S RECOMMENDATIONS.

DRAIN BASIN






KEY NOTES:


- THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED
- ② USE 4% GUTTER SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.

18" TYPE D
CONCRETE CURB & GUTTER
NTS




CURB TAPER

NTS



ACCESSIBLE PARKING AREA

NTS



ACCESSIBLE PARKING SIGN



SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

PRELIMINARY

TRUC

N

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT K1 SITE

LA CROSSE		WISCONSIN
R	EVISION SCHEDULE	
DATE	DESCRIPTION	BY
PROJECT NO.	23-30331	
FILE NAME	30331-C0-DETA	AILS
DRAWN BY	BDC	
DESIGNED BY	BDC/SMW	

TITLE

REVIEWED BY


CLIENT PROJECT NO.

ORIGINAL ISSUE DATE 03/28/2024

SITE DETAILS

SHEET

C0-22



MANHOLES 3-FT, 4-FT, 5-FT, 6-FT, 7-FT AND 8-FT DIAMETER



MANUFACTURER: STRUCTURA MODEL: TOKA RECOMMENDED FRAME: STRAIGHT 12'; SCOTS PINE/DOUGLAS FIR MOUNTING: EMBEDDED

/S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR

FESTOON POLE (BASIS OF DESIGN)

TO CONCRETE SECTION
(MIN. 4000 PSI)

12" EXPANSION JOINT W
HEAVY-DUTY SEALANT (TYP)

12" #4 DOWEL @ 12" OC
W 6" EMBEDMENT (TYP)

#4 BAR THROUGH ANCHOR
LUGS (90" BEND)

#4 BAR @ 16" OC

15" SDR 35 PVC OUTLET PIPE
(REFER TO PLANS FOR
CONTINUATION)

NEENAH R-4999-GX CASTING-

WITH TYPE C GRATE


CONCRETE SLAB REFER -

NOTES:

1. REFER TO NEENAH FOUNDARY FORMING PROCEDURES FOR ADDITIONAL INFORMATION ON THE CONSTRUCTION OF THE TRENCH DRAIN.

CONCRETE TRENCH DRAIN

NTS





SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

RELIMINARY

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

	VER POINT K1 SITE		STRUC
LA CROSSE	WISCO	NSIN	SNOO
	REVISION SCHEDULE		
DATE	DESCRIPTION	BY	U
			FOR
PROJECT NO.	23-30331		
FILE NAME 30331-C0-DETAILS			
DRAWN BY	BDC		OZ
DESIGNED BY	BDC/SMW		
REVIEWED BY	KBR		

TITLE


SITE DETAILS

ORIGINAL ISSUE DATE 03/28/2024

CLIENT PROJECT NO.

CO-23

PR



MANUFACTURER: TOURNESOL


MOUNTING: SURFACE LAID


NTS

RECOMMENDED FRAME: PITCH SMOOTH

MODEL: WCX2-721824-74 WILLSHIRE FRP RECTANGLE W/ LASER CUT SCREEN; 18" X 24" X 72"

RAISED PLANTER (BASIS OF DESIGN)






MANUFACTURER: VESTRE MODEL: 617 VROOM SEAT STRAIGHT END RECOMMENDED FRAME: POWDERCOATEDSTEEL PEARL ORANGE; STANDARD WOOD CLAY MOUNTING: SURFACE

66,4" 1687 mm 59.1"


1500 mm

BENCH (BASIS OF DESIGN)




MANUFACTURER: FORMS + SURFACES MODEL: LIGHT COLUMN BOLLARD RECOMMENDED FRAME: STAINLESS STEEL; NO SHIELD, RGBW LED MOUNTING: EMBEDDED

BOLLARD (BASIS OF DESIGN) NTS



MANUFACTURER: VESTRE MODEL: BLOC SUN BENCH RECOMMENDED FRAME: POWDERCOAT STEEL PEARL ORANGE; STANDARD WOOD MOUNTING: SURFACE

CHAISE LOUNGER (BASIS OF DESIGN)



MANUFACTURER: CUSTOM RECOMMENDED FRAME: WOOD POLE W/ MOORING ROPE MOUNTING: EMBEDDED

> DECORATIVE BOLLARD (BASIS OF DESIGN) 1/2" = 1'-0"

REVISION SCHEDULE DESCRIPTION 23-30331 30331-C0-LANDSCAPE DETAILS BDC BDC/SMW KBR CLIENT PROJECT NO. ANIM TITLE SITE DETAILS

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT. PROJECT **RIVER POINT** K1 SITE

SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

PRELIMINARY

NSTRUC

PRE

LA CROSSE WISCONSIN DATE PROJECT NO.

FILE NAME DRAWN BY **DESIGNED BY REVIEWED BY** ORIGINAL ISSUE DATE 03/28/2024

C0-24

PROJECT LOCATION: LOT 10 OF RIVER POINT DISTRICT II

CITY: LA CROSSE COUNTY/STATE: LA CROSSE COUNTY WISCONSIN

PROJECT DESCRIPTION

THE PROJECT INCLUDES CONSTRUCTION OF A NEW MIXED USE BUILDING ALONG WITH PARKING LOT, SITE AMENITIES, UTILTIES, LANDSCAPING, AND EROSION CONTROL. THE EXISTING SITE WAS AN INDUSTRIAL FACILITY THAT HAS PREVIOUSLY BEEN DEMOLISHED AND FILL PLACED TO PARTIALLY RAISE THE SITE OUT OF THE FLOODPLAIN. DEVELOPMENT OF RIVERBEND ROAD WILL PROVIDE ACCESS AND UTILITIES TO THE SITE ALONG WITH STORMWATER MANAGEMENT.

TENTATIVE CONSTRUCTION SCHEDULE (OPERATOR SHOULD PROVIDE ESTIMATED C	ONSTRUCTION SCHEDULE TO THE OWNER'S REPRESENTATIVE)
CONSTRUCTION ACTIVITIES:	ESTIMATED DATES OF SOIL DISTURBANCE ACTIVITIES:
INSTALL TEMPORARY EROSION CONTROL MEASURES	
CLEARING AND GRUBBING OPERATIONS, BUILDING EXCAVATION	
POURING FOUNDATIONS	
INSTALLATION OF SITE UTILITIES	
ROUGH GRADING OF PAVEMENT AREAS	
INSTALL CURB & GUTTER, PAVING	
TOPSOILING	
LANDSCAPING FINAL TUPE MISC	

PRE-CONSTRUCTION IMPERVIOUS SURFACE AND DISTURBED AREA CALCULATIONS

TOTAL AREA TO BE DISTURBED = 2.05 ACRES MINIMUM AREA REQUIREING WPDES PERMIT = 1.00 ACRES

PROJECT DOES REQUIRE A WPDES PERMIT

IMPERVIOUS AREA: PRE-CONSTRUCTION = 1.15 ACRES

POST-CONSTRUCTION = 1.49 ACRES

THE OWNER IS THE OWNER CO-PERMITTEE APPLYING FOR PERMIT COVERAGE AND WILL BE RESPONSIBLE FOR COMPLIANCE WITH ALL TERMS AND CONDITIONS OF THE PERMIT INCLUDING DEVELOPING THIS EROSION CONTROL PLAN AND THE LONG-TERM MAINTENANCE PLAN OF THE PERMANENT STORMWATER MANAGEMENT SYSTEM FOR THIS PROJECT (IF APPLICABLE). THE OWNER WILL ENSURE THAT THE DESCRIBED WORK IN THE EROSION CONTROL PLAN IS BEING COMPLETED BY THE OPERATOR PERMITTEE.

OWNER/PERMITTEE:

WAR EAGLE, LLC

1310 WEST WISCONSIN STREET SPARTA, WI 54656

THE PRIMARY CONTRACTOR WILL ENTER INTO A CONTRACT WITH THE OWNER TO COMPLETE THE REQUIRED WORK FOR THIS PROJECT. THE PRIMARY CONTRACTOR WILL BECOME (UNDER CONTRACT) THE OPERATOR CO-PERMITTEE APPLYING FOR PERMIT COVERAGE ON THE WPDES, AND THEREBY AGREE TO IMPLEMENT THIS EROSION CONTROL PLAN IN COOPERATION WITH THE OWNER. THE OPERATOR IS RESPONSIBLE FOR IDENTIFYING AN EROSION CONTROL SUPERVISOR PRIOR TO STARTING CONSTRUCTION (REFER TO EROSION CONTROL AMENDMENT SECTION).

THE OPERATOR WILL ENSURE THAT INDIVIDUALS OVERSEEING OR IMPLEMENTING THE EROSION CONTROL PLAN HAVE BEEN PROPERLY TRAINED AND THAT CERTIFICATIONS WILL BE MADE AVAILABLE UPON REQUEST. THIS INCLUDES ANY SUB-CONTRACTORS THAT THE OPERATOR EMPLOYS UNDER SEPARATE CONTRACT. THE OPERATOR WILL PROVIDE THE CONTACT INFORMATION FOR THE EROSION CONTROL SUPERVISOR, SITE SUPERINTENDENT/FOREMAN, AND BMP INSTALLERS. THE EROSION CONTROL SUPERVISOR SHALL BE A RESPONSIBLE EMPLOYEE OF THE PRIME CONTRACTOR AND/OR DULY AUTHORIZED BY THE PRIME CONTRACTOR TO REPRESENT THE PRIME CONTRACTOR ON ALL MATTERS PERTAINING TO THE WPDES CONSTRUCTION STORMWATER PERMIT COMPLIANCE. THE EROSION CONTROL SUPERVISOR SHALL HAVE AUTHORITY OVER ALL OPERATOR ACTIVITIES WHICH INFLUENCE WPDES PERMIT COMPLIANCE, INCLUDING GRADING, EXCAVATION, BRIDGE CONSTRUCTION, CULVERT INSTALLATION, UTILITY WORK, CLEARING/GRUBBING, DEWATERING, AND ANY OTHER OPERATION THAT INCREASES THE EROSION POTENTIAL ON THE PROJECT.

THE OPERATOR WILL PERFORM A PRECONSTRUCTION SITE VISIT TO ADDRESS ANY AREAS OF CONCERN PERTAINING TO ENVIRONMENTAL COMPLIANCE. THE OPERATOR WILL IMPLEMENT AND MAINTAIN BMPS FOR THE DURATION OF CONSTRUCTION PROJECT. THE OPERATOR WILL COMPLETE THE REQUIRED SITE INSPECTIONS.

ISG INC. HAS BEEN CONTRACTED BY THE OWNER TO DEVELOP THE EROSION CONTROL PLAN FOR THIS PROJECT. ISG INC. WILL OFFER GUIDANCE FOR COMPLIANCE WITH THE WPDES PERMIT BEFORE, DURING, AND AFTER CONSTRUCTION OF THE PROJECT.

DESIGNER ISG INC.

608-789-2034

201 MAIN STREET, SUITE 1020 LA CROSSE, WI 54610

PERMENANT STORMWATER MANAGEMENT DESIGNER:

201 MAIN STREET, SUITE 1020

LA CROSSE, WI 54610 608-789-2034

EXISTING SITE CONDITIONS, SOILS, & WATER RESOURCES

SOILS AND NATIVE TOPSOIL: NATIVE TOPSOIL WILL BE STRIPPED AND STOCKPILED FOR FINAL GRADING OPERATIONS, WHERE INDICATED IN THE CONSTRUCTION PLANS AND SPECIFICATIONS. METHODS AND EQUIPMENT TO MINIMIZE SOIL COMPACTION (IN PROPOSED INFILTRATION AREAS, DRIP LINE OF TREES TO BE PRESERVED, ETC.) SHALL BE DETERMINED BY THE OPERATOR'S EROSION CONTROL PLAN AMENDMENT. TRACKED VEHICLES ARE PREFERRED AND WHEELED VEHICLES ARE DISCOURAGED IN THESE AREAS. THE ON-SITE SOILS INCLUDE TOPSOIL, SAND FILL WITH UNDERLYING LAYERS OF ORGANIC SOILS AND CLAYSAND LEAN CLAY . REFER TO THE GEOTECHNICAL REPORT INCLUDED WITHIN THE PROJECT SPECIFICATIONS FOR MORE DETAILED SOIL INFORMATION. THE EXISTING SITE INCLUDES VEGETATED AREAS IN POOR TO FAIR CONDITION.

IMMEDIATE RECEIVING WATERS: STORMWATER FROM THIS PROJECT WILL BE CONVEYED TO CITY STORM SEWER STUBBED TO THE SITE AND ULTIMATELY DISCHARGES TO THE BLACK RIVER. A RECEIVING WATERS REVIEW WAS COMPLETED ON 03/14/2024. BASED ON THIS REVIEW THE RECEIVING WATER BLACK RIVER IS AN IMPAIRED WATER, THEREFORE SECTION 4.4 REQUIREMENTS APPLY TO THIS PROJECT.

PERMANENT STORMWATER TREATMENT SYSTEMS

THIS SITE IS A REDEVELOPMENT AND STORMWATER MANAGEMENT IS PROVIDED BY A REGIONAL TREATMENT FACILITY AS PART OF THE RIVER POINT DISTRICT DEVELOPMENT.

POTENTIAL FOR SEDIMENT AND/OR OTHER POLLUTANT(S) DISCHARGING FROM THE PROJECT SITE

THE TEMPORARY EROSION AND SEDIMENT CONTROL BMPS IN THIS EROSION CONTROL PLAN HAVE BEEN DESIGNED TO MINIMIZE THE POTENTIAL OF SEDIMENTS DISCHARGING OFF-SITE FROM A 0.5 INCH RAINFALL WITHIN A 24 HOUR PERIOD. THE NOAA ATLAS 14 POINT PRECIPITATION FREQUENCY ESTIMATE FOR THE PROJECT LOCATION WAS REVIEWED AND USED FOR ANTICIPATED INSPECTION FREQUENCY, BMP DESIGN, AND ESTIMATING CONSTRUCTION ACTIVITIES IN THIS EROSION CONTROL PLAN. ATLAS 14 RESULTS DO NOT NECESSARILY REFLECT ANY DESIGN CRITERIA IN THE PERMANENT STORMWATER MANAGEMENT SYSTEM.

ROUTINE INSPECTION AND BMP MAINTENANCE BY THE OPERATOR IS CRUCIAL IN ENSURING THE FUNCTIONALITY OF EACH BMP. STEEP SLOPES AND OTHER ENVIRONMENTALLY SENSITIVE AREAS THAT ARE AT A HIGHER RISK OF SEDIMENTATION ARE DEFINED IN THIS SWPPP (IF APPLICABLE).

CONSTRUCTION PHASING/STAGING, BUFFERS, & AREAS NOT TO BE DISTURBED

AREAS NOT TO BE DISTURBED ARE TO BE DELINEATED BEFORE WORK BEGINS. PERMITEES ARE RESPONSIBLE FOR PRESERVING A 75 FOOT NATURAL BUFFER OR (IF INFEASIBLE AND DOCUMENTED) PROVIDE REDUNDANT SEDIMENT CONTROL BMPS, WHEN A SURFACE WATER IS LOCATED WITHIN 50 FEET AND RECEIVES DRAINAGE FROM THE PROJECT'S GRADING LIMITS. THIS REQUIREMENT DOES NOT APPLY TO ADJACENT ROADSIDE DITCHES, JUDICIAL/COUNTY DITCHES, STORMWATER CONVEYANCES, STORM DRAIN INLETS, AND SEDIMENT BASINS.

EXISTING VEGETATION SHALL BE PRESERVED WHERE FEASIBLE AND LAND DISTURBING CONSTRUCTION ACTIVITIES SHALL BE STAGED TO LIMIT EXPOSED SOIL AREAS SUBJECT TO EROSION. DISTURBED PORTIONS OF THE CONSTRUCTION SITE ARE TO BE TEMPORARILY OR PERMANENTLY STABILIZED AS SOON AS PRACTICABLE AND SHALL BE INITIATED NO LATER THAN THE END OF THE NEXT WORK DAY FOLLWING THE DAY EARTH-DISTURBING ACTIVITIES IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. INITIATED STABILIZATION IS DEFINED AS COMPLETING ONE (OR MORE) OF THE FOLLOWING: SOIL PREPARATION FOR VEGETATION, MULCHING (OR OTHER TEMPORARY NON-VEGETATIVE BMP), SEEDING/PLANTING, OR SCHEDULING STABILIZATION MEASURES TO BE FULLY INSTALLED AND COMPLETED AS SOON AS PRACTICABLE.

EROSION AND SEDIMENT CONTROL BMPS

EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE USED TO PREVENT OR REDUCE THE FOLLOWING IN ORDER TO DISCHARGE NO MORE THAN 5 TONS PER ACRE PER YEAR OF SEDIMENT

THE OPERATOR SHALL CLEARLY IDENTIFY THE CONTRACTOR(S) AND SUBCONTRACTOR(S) THAT ARE RESPONSIBLE FOR THE INSTALLATION, OPERATION, AND CONTINUED MAINTENANCE OF ALL TEMPORARY AND PERMANENT WATER QUALITY MANAGEMENT BMPS, AS WELL AS ALL EROSION PREVENTION AND SEDIMENT CONTROL BMPS, FOR THE DURATION OF THE CONSTRUCTION WORK AT THE SITE, UNTIL FINAL STABILIZATION IS ACHIEVED. ALL BMPS MUST BE ADEQUATELY LOCATED, DESIGNED, INSTALLED, AND MAINTAINED TO PREVENT EROSION FROM A MINIMUM 0.5 INCH TOTAL RAINFALL EVENT WITHIN 24 HOURS.

ALL NONFUNCTIONAL BMPS MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMPS BY THE END OF THE NEXT BUSINESS DAY AFTER DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS UNLESS ANOTHER TIME FRAME IS SPECIFIED IN THE EROSION CONTROL PLAN. ALL ERODED MATERIAL THAT LEAVES THE SITE SHALL BE COLLECTED BY THE OPERATOR AND RETURNED TO THE SITE AT THE OPERATOR'S EXPENSE AND INCIDENTAL TO THE PROJECT COST.

TEMPORARY STABILIZATION BMPS SHALL ONLY BE IMPLEMENTED WHEN PERMANENT STABILIZATION BMPS CANNOT BE IMPLEMENTED WITHIN A REASONABLE TIMEFRAME FOR EXPOSED SOILS.

DEWATERING, STREAM DIVERSION, OR BASIN DRAINING MAY BE REQUIRED DURING CONSTRUCTION OF THIS PROJECT. WHEN DEWATERING IS REQUIRED, THE CONTRACTOR SHALL SUBMIT A DEWATERING PLAN AND NARRATIVE TO THE PROJECT ENGINEER FOR APPROVAL PRIOR TO UNDERTAKING THESE ACTIVITIES. DEWATERING PLAN MUST BE DESIGNED IN ACCORDANCE WITH WI DNR TECHNICAL STANDARD 1061 INCLUDE BMP'S TO PREVENT SEDIMENT TRANSPORT, EROSION, AND ADVERSE IMPACTS TO DOWNSTREAM RECEIVING WATERS. THE DEWATERING PLAN MUST ALSO INCLUDE ANY SPECIFIC CHEMICAL TREATMENTS (FLOC, POLYMERS, ETC.) THAT WILL BE USED. THE DEWATERING PLAN AND DNR APPROPRIATIONS PERMIT WILL BECOME PART OF THE EROSION CONTROL PLAN. WATER THAT IS TURBID OR HAS SEDIMENT MUST BE DISCHARGED TO A TEMPORARY OR PERMANENT SEDIMENTATION BASIN (AND/OR OTHER APPROPRIATE BMPS) ON THE PROJECT SITE WHENEVER POSSIBLE. DISCHARGE FROM THE TEMPORARY OR PERMANENT SEDIMENTATION BASIN MUST BE VISUALLY CHECKED TO ENSURE ADEQUATE TREATMENT IS OBTAINED IN THE BASIN AND THAT NUISANCE CONDITIONS. IMPACTS TO WETLANDS, AND EROSION IN RECEIVING CHANNELS OR ON DOWNSLOPE PROPERTIES WILL NOT RESULT FROM THE DISCHARGE. THE DISCHARGE MUST BE DISPERSED OVER NATURAL ROCK RIPRAP, SAND BAGS, PLASTIC SHEETING, OR OTHER ACCEPTED ENERGY DISSIPATION MEASURES. ADEQUATE SEDIMENTATION CONTROL MEASURES AND ADDITIONAL FILTRATION BMPS ARE REQUIRED FOR DISCHARGE WATER THAT CONTAINS SUSPENDED SOLIDS, OIL, OR GREASE.

SEQUENCE OF CONSTRUCTION/TIMING OF BMP INSTALLATION

NO CONSTRUCTION OPERATIONS, INCLUDING REMOVALS, THAT REQUIRE EROSION & SEDIMENT CONTROL PER THE EROSION CONTROL PLAN CAN COMMENCE UNTIL THE OPERATOR'S EROSION CONTROL SUPERVISOR CERTIFIES THE PROPER INSTALLATION OF BMP'S AND A CHAIN OF RESPONSIBILITY FOR EROSION CONTROL PLAN IMPLEMENTATION IS CREATED FOR ALL OPERATORS ON THE SITE. PERIMETER SEDIMENT CONTROLS (SILT FENCE, INLET PROTECTION, CONSTRUCTION ENTRANCES, ETC.) SHALL BE INSTALLED PRIOR TO THE START OF CONSTRUCTION. THESE PRACTICES SHALL REMAIN IN PLACE UNTIL FINAL STABILIZATION IS ACHIEVED. OPERATOR SHALL IMPLEMENT THE NECESSARY ON SITE BMP'S IN ACCORDANCE WITH THE WPDES PERMIT REQUIREMENTS TO PREVENT NUISANCE CONDITIONS FROM ANY DISCHARGES UNDER COVERAGE OF THE WPDES PERMIT. IN SOME CASES, MULTIPLE OR REDUNDANT APPLICATIONS OF SOME BMP'S MAY BE NEEDED TO MEET THESE REQUIREMENTS.

TEMPORARY & PERMANENT EROSION PREVENTION BMPS

TEMPORARY/PERMANENT DRAINAGE DITCHES & SWALES: THE NORMAL WETTED PERIMETER (2-YEAR, 24-HOUR PRECIPITATION EVENT) OF ANY TEMPORARY OR PERMANENT DRAINAGE DITCH, CHANNEL, OR SWALE THAT DRAINS WATER FROM ANY PORTION OF THE CONSTRUCTION SITE, OR DIVERTS WATER AROUND THE SITE, MUST BE STABILIZED WITHIN THE LAST 200 LINEAL FEET FROM THE PROPERTY EDGE, OR FROM THE POINT OF DISCHARGE INTO ANY SURFACE WATER WITHIN 24 HOURS OF CONNECTION. STABILIZATION REMAINING OF THE REMAINING PORTIONS OF THE CHANNEL MUST BE STABILIZED WITHIN 14 DAYS. ALL STORMWATER CONVEYANCE CHANNELS MUST USE EROSION CONTROL AND VELOCITY DISSIPATION DEVICES WITHIN AND ALONG THE LENGTH OF THE CHANNEL AND AT ANY OUTLETS. TEMPORARY OR PERMANENT DITCHES OR SWALES THAT ARE BEING USED AS A TEMPORARY SEDIMENT CONTAINMENT SYSTEM (WITH PROPERLY DESIGNED ROCK DITCH CHECKS, BIO ROLLS, SILT DIKES ETC.) DO NOT NEED TO BE STABILIZED. THESE AREAS HOWEVER MUST BE STABILIZED WITHIN 24 HOURS AFTER NO LONGER BEING USED AS A SEDIMENT CONTAINMENT SYSTEM. MULCH, HYDROMULCH, TACKIFIER, OR POLYARCRYLAMIDE BELOW THE WETTED PERIMETER OF A DITCH, SWALE, OR OTHER SURFACE WATER CONVEYANCE IS NOT ACCEPTABLE STABILIZATION.

EROSION CONTROL BLANKETS/MATS: OPERATOR SHALL VERIFY DURING REGULAR INSPECTIONS THAT NO GULLIES, RILLS, OR SCOUR HOLES HAVE FORMED UNDER EROSION CONTROL BLANKETS AND MATS. ALL REPAIRS MUST BE COMPLETED WITHIN 24 HOURS OF DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS. USE THE REQUIRED CLASS AND TYPE OF EROSION MAT THE PLANS SHOW OR IS SPECIFIED.

MULCH: OPERATOR MUST APPLY MULCH IN A UNIFORM PATTERN OVER THE DISTURBED SOILS, TO ACHIEVE A MINIMUM OF 90% GROUND COVER.

METHOD A, NETTING: SECURLY ANCHOR MULCHING MATERIAL BY APPROVED NETTING AND PEGS OR STAPLES METHOD B, TACKIFIER: UTILIZE A TACKIFIER TO TREAT OR APPLY TO THE MULCHING MATERIAL

DUST CONTROL: DUST FROM THE SITE WILL BE CONTROLLED BY INCREASED STREET SWEEPING AND/OR USING A MOBILE PRESSURE-TYPE DISTRIBUTOR TRUCK TO APPLY POTABLE WATER TO DISTURBED AREAS. THE MOBILE UNIT WILL APPLY WATER AT A RATE NECESSARY TO PREVENT RUNOFF AND PONDING.

STORM SEWER OUTLETS: PIPE OUTLETS MUST HAVE TEMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS AFTER HYDRAULIC CONNECTION TO A RECEIVING SURFACE WATER.

TEMPORARY WINTER COVER: AREAS OF EXPOSED SOILS THAT ARE NOT COMPLETED BEFORE THE WINTER SHALL BE STABILIZED BEFORE CONSTRUCTION IS COMPLETED FOR THE SEASON.

TEMPORARY & PERMANENT SEDIMENT CONTROL BMPS

DOWNGRADIENT SYSTEMS: IF THE DOWNGRADIENT TREATMENT SYSTEM IS OVERLOADED, ADDITIONAL UP GRADIENT SEDIMENT CONTROL PRACTICES OR REDUNDANT BMPS MUST BE INSTALLED TO ELIMINATE THE OVERLOADING, AND THE EROSION CONTROL PLAN MUST BE AMENDED TO IDENTIFY THESE ADDITIONAL PRACTICES.

PERIMETER CONTROL BMPS (SILT FENCES, CHIP/SLASH MULCH SACKS, BIOROLLS, FLOATING SILT CURTAIN, ETC.): PERIMETER CONTROL BMPS SHALL BE INSTALLED ON ALL DOWNGRADIENT PERIMETERS AND UPGRADIENT OF ANY BUFFER AREAS, PRIOR TO INITIATING UPGRADIENT LAND DISTURBANCE ACTIVITIES. UPLAND PERIMETER CONTROLS BMPS SHALL BE PLACED AS CLOSE AS POSSIBLE TO FOLLOW A SINGLE CONTOUR ELEVATION. ALL PERIMETER CONTROL DEVICES MUST BE REPAIRED, REPLACED, OR MAINTAINED WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/2 OF THE HEIGHT OF THE DEVICE. FLOATING SILT CURTAIN SHALL BE INSTALLED AS CLOSE TO THE SHORELINE AS POSSIBLE FOR SHORELAND/IN-WATER SHORT-TERM CONSTRUCTION ACTIVITIES. IMMEDIATELY AFTER THE SHORT-TERM ACTIVITY IN THAT AREA IS COMPLETE, AN UPLAND PERIMETER CONTROL MUST BE INSTALLED IF EXPOSED SOILS CONTINUE

TEMPORARY SEDIMENTATION BASINS AND TRAPS: THE BASIN INTAKE MUST BE DESIGNED IN ACCORDANCE WITH WI DNR TECHNICAL STANDARD 1063. THE BASIN SHALL WITHDRAW WATER FROM THE SURFACE. PREVENT SHORT CIRCUITING AND THE DISCHARGE OF FLOATING DEBRIS. INCLUDE AN EMERGENCY OVERFLOW ABOVE THE LIVE STORAGE ELEVATION. AND PROVIDE ENERGY DISSIPATION AT THE BASIN OUTLET. BASINS MUST BE DRAINED AND SEDIMENT REMOVED WHEN THE DEPTH OF COLLECTED SEDIMENT IN THE BASIN REACHES 1/2 THE LIVE STORAGE VOLUME.

TEMPORARY STOCKPILES: ALL STOCKPILES MUST HAVE SILT FENCE OR EQUIVALENT PERIMETER SEDIMENT CONTROLS IMPLEMENTED AND MAINTAINED AT ALL TIMES. PILES CANNOT BE PLACED IN BUFFER AREAS OR SURFACE WATERS, INCLUDING STORMWATER CONVEYANCES SUCH AS CURB AND GUTTER SYSTEMS, OR CONDUITS AND DITCHES UNLESS THERE IS A BYPASS IN PLACE TO PREVENT STORMWATER RUN-ON INTO THE STOCKPILE. STABILIZATION ON TEMPORARY STOCKPILES WITHOUT SIGNIFICANT SILT, CLAY OR ORGANIC COMPONENTS IS NOT REQUIRED.

CONSTRUCTION SITE ENTRANCE/VEHICLE TRACKING: OPERATOR MUST MINIMIZE SEDIMENT FROM LEAVING THE CONSTRUCTION SITE (OR ONTO STREETS WITHIN THE SITE) BY IMPLEMENTING BMPS SUCH AS ROCK PADS, SLASH MULCH, CONCRETE OR STEEL WASH RACKS, OR EQUIVALENT SYSTEMS. STREET SWEEPING MUST BE USED DAILY DURING CONSTRUCTION OPERATIONS IF SUCH BMPS ARE NOT ADEQUATE TO PREVENT SEDIMENT FROM BEING TRACKED ONTO THE STREET. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES (ON AND OFF-SITE) WITHIN 24 HOURS OF DISCOVERY, OR SOONER AS DIRECTED BY THE PROJECT OWNER. MULTIPLE STREET SWEEPINGS AT THE OPERATOR'S EXPENSE MAY BE REQUIRED ON ALL ENTRY/EXIT POINTS TO THE SITE AT THE DISCRETION OF THE PROJECT OWNER.

SURFACE WATERS: INCLUDING OFF-SITE AND DOWNSTREAM DRAINAGE DITCHES, CATCH BASINS, AND CONVEYANCE SYSTEMS, MUST BE INSPECTED FOR EVIDENCE OF EROSION AND SEDIMENT DEPOSITION. THE REMOVAL AND STABILIZATION OF EXPOSED SOILS MUST TAKE PLACE WITHIN SEVEN (7) DAYS OF DISCOVERY UNLESS PRECLUDED BY LEGAL, REGULATORY, OR PHYSICAL ACCESS CONSTRAINTS. IF PRECLUDED, REMOVAL AND STABILIZATION MUST TAKE PLACE WITHIN SEVEN (7) CALENDAR DAYS OF OBTAINING ACCESS. THE PERMITTEES ARE RESPONSIBLE FOR CONTACTING ALL LOCAL, REGIONAL, STATE AND FEDERAL AGENCIES AND RECEIVING ANY APPLICABLE PERMITS, PRIOR TO CONDUCTING ANY WORK.

INLET PROTECTION: ALL STORM DRAIN INLETS (INCLUDING DOWNGRADIENT, OFF-SITE) MUST BE PROTECTED BY APPROPRIATE BMPS DURING CONSTRUCTION UNTIL ALL SOURCES WITH POTENTIAL FOR DISCHARGING TO THE INLET HAVE BEEN STABILIZED. SILT FENCE IS NOT AN ACCEPTABLE CATCH BASIN INLET PROTECTION BMP. CONTACTOR SHALL CLEAN, REMOVE AND DISPOSE OF SEDIMENT, AND/OR REPLACE STORM DRAIN INLET PROTECTION ON A ROUTINE BASIS TO ENSURE THE DEVICE IS FULLY FUNCTIONAL PRIOR TO THE NEXT FORECASTED PRECIPITATION EVENT (30% OR GREATER). INLET PROTECTION MAY BE REMOVED FOR A PARTICULAR INLET IF A SPECIFIC SAFETY CONCERN (STREET FLOODING/FREEZING) HAS BEEN IDENTIFIED BY THE PERMITTEE(S) OR THE JURISDICTIONAL AUTHORITY (E.G. CITY/COUNTY/TOWNSHIP/DOT ENGINEER). WRITTEN CORRESPONDENCE REGARDING THE NEED FOR REMOVAL MUST BE DOCUMENTED IN THE EROSION CONTROL PLAN.

CHEMICAL TREATMENTS: OPERATOR MUST AMEND THE SWPEROSION CONTROL PLAN TO INCLUDE THE INTENDED USES AND LOCATIONS OF FLOCCULANTS, POLYMERS, AND OTHER SEDIMENTATION TREATMENT CHEMICALS. CHEMICAL TREATMENTS MAY ONLY BE APPLIED IN AREAS WHERE TREATED STORMWATER IS DIRECTED TO A RECEIVING SEDIMENT CONTROL SYSTEM (NOT DIRECTLY DISCHARGED TO NATURAL WATER BODIES). THIS INCLUDES DOCUMENTING THE EXPECTED SOIL TYPES, MANUFACTURER'S RECOMMENDED DOSING, APPLICATION RATES/QUANTITIES, AND MONITORING RESULTS (TURBIDITY, PH).

POLLUTION PREVENTION MANAGEMENT MEASURES

- THE FOLLOWING PREVENTATIVE MEASURES SHALL BE INCORPORATED: MAINTENANCE OF EXISTING VEGETATION, ESPECIALLY ADJACENT TO SURFACE WATERS WHENEVER POSSIBLE;
 - MINIMIZATION OF SOIL COMPACTION AND PRESERVATION OF TOP-SOIL MINIMIZATION OF LAND DISTURBING CONSTRUCTION ACTIVITY ON SLOPES OF 20% OR MORE;
 - DEVELOPMENT OF SPILL PREVENTION AND RESPONSE PROCEDURES.

POTENTIAL SOURCES OF UNAUTHORIZED DISCHARGES CONSTRUCTION ACTIVITIES INCLUDE WASTEWATER DISCHARGES FROM WASHOUT AND CLEANOUT OF STUCCO. PAINT. FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS; FUELS, OILS AND OTHER POLLUTANTS USED IN VEHICLE OPERATION AND MAINTENANCE; AND SOAPS OR SOLVENTS USED IN VEHICLE AND/OR EQUIPMENT WASHING.

THE PERMITTEE SHALL NOTIFY THE DEPARTMENT OF ANY RELEASE OR SPILL O FA HAZARDOUS SUBSTANCE TO THE ENVIRONMENT IN ACCORDANCE WITH S. 292.11, WIS. STATS., AND CH. CR 706 WIS. ADM. CODE AT (800) 943-0003.

INSPECTIONS & MAINTENANCE

THE OPERATOR MUST INSPECT THE ENTIRE CONSTRUCTION SITE AT LEAST ONCE EVERY SEVEN (7) DAYS DURING ACTIVE CONSTRUCTION AND WITHIN 24 HOURS AFTER A RAINFALL EVENT GREATER THAN 0.5 INCHES IN 24 HOURS. THE OPERATOR SHALL PROVIDE A RAINFALL GAUGE ON-SITE, WITHIN ONE MILE OF THE SITE, OR SOURCE OF THE WEATHER REPORTING SYSTEM THAT USES SITE SPECIFIC RAINFALL DATA FROM RADAR SUMMARIES. THE LOCATION AND SOURCE OF THE RAINFALL GAUGE OR REPORTING SYSTEM MUST BE DOCUMENTED IN THE FIRST EROSION CONTROL INSPECTION REPORT, ALL MAINTENANCE SHALL BE DONE IN ACCORDANCE WITH TECHNICAL STANDARDS DEVELOPED PURSUANT TO SUBCH, V OF CH. NR 151, WIS. ADM. CODE. ALL

SHEET NOT VALID UNLESS THIS TEXT IS COLOR

Z

 $\mathsf{I}\mathsf{H}\mathsf{I}\mathsf{S}$ DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT

PROJECT

RIVER POINT

K1 SITE

LA CROSSE WISCONSIN REVISION SCHEDULE DATE DESCRIPTION

PROJECT NO. 23-30331 FILE NAME 30331-C1-EROSION DRAWN BY BDC BDC/SMW **DESIGNED BY** KBR **REVIEWED BY** ORIGINAL ISSUE DATE 03/28/2024 CLIENT PROJECT NO.

TITLE

EROSION NARRATIVE

INSPECTIONS AND MAINTENANCE CONDUCTED MUST BE RECORDED IN WRITING BY THE OPERATOR AND RETAINED WITH THE EROSION CONTROL PLAN. THE DEPARTMENT HAS DEVELOPED A MODEL INSPECTION REPORT AVAILABLE AT HTTP://DNR.WI.GOV/TOPIC/STORMWATER/CONSTRUCTION/FORMS.HTML OR AVAILABLE UPON REQUEST FOR THE PROJECT OWNER. RECORDS OF EACH INSPECTION AND MAINTENANCE ACTIVITY SHALL INCLUDE:

A. DATE, TIME AND EXACT LOCATION OF THE INSPECTION;

B. NAME OF PERSON(S) CONDUCTING INSPECTIONS;

C. AN ASSESSMENT OF THE CONDITION OF EROSION AND SEDIMENT CONTROLS;

D. A DESCRIPTION OF ANY EROSION AND SEDIMENT CONTROL INSTALLATION OR MAINTENANCE PERFORMED IN RESPONSE TO THE INSPECTION; E. DESCRIPTION OF THE PRESENT PHASE OF CONSTRUCTION AT THE SITE AND ANY SCHEDULE MODIFICATIONS THAT MAY INCREASE SEDIMENT DISCHARGE.

THE OWNER SHALL BE IN CHARGE OF THE LONG-TERM MAINTENANCE OF PERMANENT BMPS.

EROSION CONTROL PLAN AMENDMENTS & RECORD KEEPING

EROSION CONTROL PLAN AMENDMENTS AND SITE PLANS WILL BE PREPARED BY THE OPERATOR AND SUBMITTED TO THE OWNER FOR REVIEW AND WRITTEN APPROVAL BY THE PROJECT OWNER (OR DESIGNATED REPRESENTATIVE). ALL OWNER ACCEPTED AND DENIED EROSION CONTROL PLAN AMENDMENTS AND SITE PLANS MUST BE RECORDED IN WRITING AND RETAINED WITH THE EROSION CONTROL PLAN.

THE EROSION CONTROL PLAN SHALL BE AMENDED IF:

- THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION OR MAINTENANCE AT THE CONSTRUCTION SITE, WHICH HAS THE REASONABLE POTENTIAL FOR THE DISCHARGE OF POLLUTANTS AND WHICH HAS NOT OTHERWISE BEEN ADDRESSED IN THE EROSION CONTROL AND STORM WATER MANAGEMENT PLANS;
- THERE IS A CHANGE IN THE SEQUENCE, SCHEDULE, OR PHASING OF CONSTRUCTION AT THE CONSTRUCTION SITE WHICH HAS A REASONABLE POTENTIAL TO CAUSE AN
- EXCEEDANCE OF THE 5 TONS PER ACRE PER YEAR SEDIMENT PERFORMANCE STANDARD; THE ACTIONS REQUIRED BY THE EROSION CONTROL AND STORM WATER MANAGEMENT PLANS FAIL TO REDUCE THE IMPACTS OF POLLUTANTS CARRIED BY CONSTRUCTION SITE STORM WATER RUNOFF.

FOR CONSTRUCTION SITES FOR WHICH THERE HAS BEEN EARLIER DEPARTMENT REVIEW OF THE EROSION

CONTROL AND STORM WATER MANAGEMENT PLANS, IF THE PERMITTEE IDENTIFIES CHANGES NEEDED IN EITHER PLAN, THE PERMITTEE SHALL NOTIFY THE DEPARTMENT AT LEAST 5 WORKING DAYS PRIOR TO MAKING THE

CHANGES IN THE PLAN.

THE EROSION CONTROL PLAN (ORIGINAL OR COPIES), ALL CHANGES TO THE EROSION CONTROL PLAN, PROJECT MANUAL, AND INSPECTIONS/MAINTENANCE RECORDS MUST BE KEPT AT THE SITE DURING CONSTRUCTION BY THE OPERATOR WHO HAS OPERATIONAL CONTROL OF THAT PORTION OF THE SITE. THE EROSION CONTROL PLAN CAN BE KEPT IN THE FIELD OFFICE OR ON SITE VEHICLE DURING NORMAL WORKING HOURS. THE PERMITEES MUST KEEP AND MAKE AVAILABLE TO FEDERAL, STATE, AND LOCAL OFFICIALS WITHIN FIVE DAYS THE EROSION CONTROL PLAN, OTHER STORMWATER RELATED PERMITS, RECORDS OF ALL INSPECTION/MAINTENANCE, ALL PERMANENT OPERATIONS AND MAINTENANCE AGREEMENTS, ALL REQUIRED CALCULATIONS FOR DESIGN OF THE TEMPORARY AND PERMANENT STORMWATER MANAGEMENT SYSTEMS AND OTHER INFORMATION REQUIRED BY THE GENERAL PERMIT FOR THREE YEARS FOLLOWING THE NOTICE OF TERMINATION.

NOTICE OF TERMINATION
THE PERMITEE SHALL SIGN AND SUBMIT A NOTICE OF TERMINATION (NOT) (AVAILABLE THROUGH THE DEPARMENT AT http://dnr.wi.gov/topic/stormwater/construction/forms.html) TO THE DEPARTMENT WITHIN 45 DAYS AFTER FINAL STABILIZATION, REMOVAL OF TEMPORARY EROSION CONTROL BMPS AND ALL LAND DISTURBING CONSTRUCTION ACTIVITY UNDER THIS PERMIT

FINAL STABILIZATION MEANS THAT ALL LAND DISTURBING CONSTRUCTION ACTIVITIES AT THE CONSTRUCTION SITE HAVE BEEN COMPLETED AND THAT A UNIFORM PERENNIAL VEGETATIVE COVER HAS BEEN ESTABLISHED WITH A

DENSITY OF AT LEAST 70% OF THE COVER FOR THE UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES OR THAT EMPLOY EQUIVALENT PERMANENT STABILIZATION MEASURES.

TERMINATION OF COVERAGE UNDER THIS PERMIT SHALL BE EFFECTIVE UPON THE DEPARTMENT'S WRITTEN CONFIRMATION OF PERMIT TERMINATION TO THE PERMITEE.

EROSION CONTROL NOTES:

- POST WDNR CERTIFICATE OF PERMIT COVERAGE ON SITE AND MAINTAIN UNTIL CONSTRUCTION ACTIVITIES HAVE CEASED, THE SITE IS STABILIZED, AND A NOTICE OF TERMINATION
- KEEP A COPY OF THE CURRENT EROSION CONTROL PLAN ON SITE THROUGHOUT THE DURATION OF THE PROJECT.
- SUBMIT PLAN REVISIONS OR AMENDMENTS TO THE WDNR AT LEAST 5 DAYS PRIOR TO FIELD IMPLEMENTATION. THE CONTRACTOR IS RESPONSIBLE FOR ROUTINE SITE INSPECTIONS AT LEAST ONCE EVERY 7 DAYS AND WITHIN 24 HOURS AFTER A RAINFALL EVENT OF 0.5 INCHES OR GREATER.
- KEEP INSPECTION REPORTS ON-SITE AND MAKE THEM AVAILABLE UPON REQUEST. INSPECT AND MAINTAIN ALL INSTALLED EROSION CONTROL PRACTICES UNTIL THE CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.
- WHEN POSSIBLE: PRESERVE EXISTING VEGETATION (ESPECIALLY ADJACENT TO SURFACE WATERS), MINIMIZE LAND-DISTURBING CONSTRUCTION ACTIVITY ON SLOPES OF 20% OR MORE, MINIMIZE SOIL COMPACTION, AND PRESERVE TOPSOIL.
- REFER TO THE WDNR STORMWATER CONSTRUCTION TECHNICAL STANDARDS AT http://dnr.wi.gov/topic/stormwater/standards/const_standards.html
- INSTALL PERIMETER EROSION CONTROLS AND ROCK TRACKING PAD CONSTRUCTION ENTRANCE(S) PRIOR TO ANY LAND-DISTURBING ACTIVITIES, INCLUDING CLEARING AND GRUBBING. USE WDNR TECHNICAL STANDARD STONE TRACKING PAD AND TIRE WASHING #1057 FOR ROCK CONSTRUCTION ENTRANCE(S).
- INSTALL INLET PROTECTION PRIOR TO LAND-DISTURBING ACTIVITIES IN THE CONTRIBUTING DRAINAGE AREA AND/OR IMMEDIATELY UPON INLET INSTALLATION. COMPLY WITH WDNR TECHNICAL STANDARD STORM DRAIN INLET PROTECTION FOR CONSTRUCTION SITES #1060.
- STAGE CONSTRUCTION GRADING ACTIVITIES TO MINIMIZE THE CUMMULATIVE EXPOSED CONDUCT TEMPORARY GRADING FOR EROSION CONTROL PER WDNR TECHNICAL STANDARD TEMPORARY GRADING PRACTICES FOR EROSION CONTROL #1067.
- PERMITTING OF GROUNDWATER DEWATERING IS THE RESPONSIBILITY OF THE CONTRACTOR. GROUNDWATER DEWATERING IS SUBJECT TO A DNR WASTEWATER DISCHARGE PERMIT AND A DNR HIGH CAPACITY WELL APPROVAL IF CUMULATIVE PUMP CAPACITY IS 70 GPM OR MORE. (REV. FEBRUARY 2017)
- PROVIDE ANTI-SCOUR PROTECTION AND MAINTAIN NON-EROSIVE FLOW DURING DEWATERING. PERFORM DEWATERING OF ACCUMULATED SURFACE RUNOFF IN ACCORDANCE
- WITH WDNR TECHNICAL STANDARD DE-WATERING #1061. (REV. FEBRUARY 2017)
- COMPLETE AND STABILIZE SEDIMENT BASINS/TRAPS OR WET PONDS PRIOR TO MASS LAND DISTURBANCE TO CONTROL RUNOFF DURING CONSTRUCTION. REMOVE SEDIMENT AS NEEDED TO MAINTAIN 3 FEET OF DEPTH TO THE OUTLET, AND PROPERLY DISPOSE OF SEDIMENT REMOVED DURING MAINTENANCE (REFER TO NR 528). CONSTRUCT AND MAINTAIN THE SEDIMENT BASIN PER WDNR TECHNICAL STANDARD SEDIMENT BASIN #1064 AND SEDIMENT TRAP # 1063.
- CONSTRUCT AND PROTECT THE BIOINFILTRATION BASIN AND VEGETATION FROM RUNOFF AND SEDIMENT DURING CONSTRUCTION. REFERENCE THE WONR TECHNICAL STANDARD BIORETENTION FOR INFILTRATION # 1004.
- INSTALL AND MAINTAIN SILT FENCING PER WDNR TECHNICAL STANDARD SILT FENCE REMOVE SEDIMENT FROM BEHIND SILT FENCES AND SEDIMENT BARRIERS BEFORE SEDIMENT REACHES A DEPTH THAT IS EQUAL TO ONE-HALF OF THE FENCE AND/OR BARRIER HEIGHT.
- REPAIR BREAKS AND GAPS IN SILT FENCES AND BARRIERS IMMEDIATELY. REPLACE DECOMPOSING STRAW BALES (TYPICAL BALE LIFE IS 3 MONTHS). LOCATE, INSTALL, AND MAINTAIN STRAW BALES PER WDNR TECHNICAL STANDARD DITCH CHECKS #1062.
- INSTALL AND MAINTAIN FILTER SOCKS IN ACCORDANCE WITH WDNR TECHNICAL STANDARD INTERIM MANUFACTURED PERIMETER CONTROL AND SLOPE INTERRUPTION PRODUCTS
- IMMEDIATELY STABILIZE STOCKPILES AND SURROUND STOCKPILES AS NEEDED WITH SILT FENCE OR OTHER PERIMETER CONTROL IF STOCKPILES WILL REMAIN INACTIVE FOR 7 DAYS OR LONGER.
- IMMEDIATELY STABILIZE ALL DISTURBED AREAS THAT WILL REMAIN INACTIVE FOR 14 DAYS OR LONGER. BETWEEN SEPTEMBER 15 AND OCTOBER 15: STABILZE WITH MULCH, TACKIFIER, AND A PERENNIAL SEED MIXED WITH WINTER WHEAT, ANNUAL OATS, OR ANNUAL RYE, AS APPROPRIATE FOR REGION AND SOIL TYPE OCTOBER 15 THROUGH COLD WEATHER: STABILIZE WITH A POLYMER AND DORMANT SEED MIX. AS APPROPRIATE FOR REGION AND SOIL TYPE.
- STABILIZE AREAS OF FINAL GRADING WITHIN 7 DAYS OF REACHING FINAL GRADE. SWEEP/CLEAN UP ALL SEDIMENT/TRASH THAT MOVES OFF-SITE DUE TO CONSTRUCTION ACTIVITY OR STORM EVENTS BEFORE THE END OF THE SAME WORKDAY. SEPARATE
- SWEPT MATERIALS (SOILS AND TRASH) AND DISPOSE OF APPROPRIATELY.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTROLLING DUST PER WDNR TECHNICAL STANDARD DUST CONTROL ON CONSTRUCTION SITES # 1068.
- PROPERLY DISPOSE OF ALL WASTE AND UNUSED BUILDING MATERIALS (INCLUDING GARBAGE, DEBRIS, CLEANING WASTES, OR OTHER CONSTRUCTION MATERIALS) AND DO NOT ALLOW THESE MATERIALS TO BE CARRIED BY RUNOFF INTO THE RECEIVING CHANNEL
- OR CONSTRUCTION DEBRIS THAT WILL BE HAULED OFF-SITE FOR DISPOSAL. THE DEPOSITED OR STOCKPILED MATERIAL NEEDS TO INCLUDE PERIMETER SEDIMENT CONTROL MEASURES (SUCH AS SILT FENCE, HAY BALES, FILTER SOCKS, OR COMPACTED EARTHEN BERMS).

THE CONTRACTOR IS RESPONSIBLE FOR UPDATING THE LAND DISTURBANCE PERMIT TO INDICATE THE ANTICIPATED OR LIKELY DISPOSAL LOCATIONS FOR ANY EXCAVATED SOILS

- FOR NON-CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED SLOPES, PROVIDE CLASS I TYPE A EROSION CONTROL MATTING. SELECT EROSION MATTING FROM APPROPRITE MATRIX IN WISDOT'S WIDOT PRODUCT ACCEPTABILITY LIST (PAL); INSTALL AND MAINTAIN PER WDNR TECHNICAL STANDARD NON-CHANNEL EROSION MAT #1052.
- FOR CHANNELIZED FLOW ON DISTURBED OR CONSTRUCTED AREAS, PROVIDE CLASS I TYPE B EROSION CONTROL MATTING. SELECT EROSION MATTING FROM APPROPRIATE MATRIX IN WISDOT'S WIDOT PRODUCT ACCEPTABILITY LIST (PAL); INSTALL AND MAINTAIN PER WDNR TECHNICAL STANDARD CHANNEL EROSION MAT #1053.
- MAKE PROVISIONS FOR WATERING DURING THE FIRST 8 WEEKS FOLLOWING SEEDING OR PLANTING OF DISTURBED AREAS WHENEVER MORE THAN 7 CONSECUTIVE DAYS OF DRY WEATHER OCCUR.
- THE CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE WDNR REMEDIATION AND WASTE MANAGEMENT REQUIREMENTS FOR HANDLING AND DISPOSING OF CONTAMINATED MATERIALS. SITE SPECIFIC INFORMATION FOR AREAS WITH KNOWN OR SUSPECTED SOIL AND/OR GROUNDWATER CONTAMINATION CAN BE FOUND ON WDNR'S
- BUREAU OF REMEDIATION AND REDEVELOPMENT TRACKING SYSTEM (BRRTS) PUBLIC DATABASE AT: HTTP://DNR.WI.GOV/BOTW/ THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A SPILL PLAN. REFER TO THIS DOCUMENT IF THERE IS A DISCHARGE OF SEDIMENT AND/OR OTHER CONTAMINANTS. A SPILL
- PLAN IS REQUIRED IF THERE IS POTENTIAL TO DISCHARGE CONTAMINANTS TO WATERS OF THE STATE. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING A FRAC OUT PLAN IF DRILLING IS TO OCCUR. REFER TO THIS DOCUMENT IF AN INADVERTANT DISCHARGE OF DRILLING FLUIDS
- ("FRAC OUT") OCCURS. A SPILL PLAN IS REQUIRED IF THERE IS POTENTIAL TO DISCHARGE CONTAMINANTS TO WATERS OF THE STATE.
- INSTALL AND MAINTAIN A CONCRETE WASHOUT BASIN PER EPA 833-F-11-006: HTTPS://WWW3.EPA.GOV/NPDES/PUBS/CONCRETEWASHOUT.PDF. REQUIRE USE BY ALL CONCRETE CONTRACTORS. LIQUID MAY BE REUSED IN CONCRETE MIXING, EVAPORATED, OR DISPOSED OF AS WASTEWATER.

~

Z

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED. COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT

K1 SITE


LA CROSSE WISCONSIN **REVISION SCHEDULE** DATE DESCRIPTION

PROJECT NO. 23-30331 **FILE NAME** 30331-C1-EROSION DRAWN BY BDC BDC/SMW DESIGNED BY **REVIEWED BY** KBR ORIGINAL ISSUE DATE 03/28/2024 CLIENT PROJECT NO.

TITLE

EROSION CONTROL **NARRATIVE**

C1-11



STABILIZED CONSTRUCTION EXIT


PLASTIC SHEETING EDGE SHALL BE BURIED OR HELD IN PLACE WITH SUITABLE MATERIAL (SAND, SAND BAGS, ROCK, METAL, WOOD LOGS, ETC.) NATIVE -MATERIAL -MINIMUM 10-MIL THICK PLASTIC SHEETING OR APPROVED EQUAL 1' DEEP 5'x10'x3' CONCRETE-IMPERVIOUS CLAY LINER WASHOUT AREA OR OTHER SUITABLE ZERO FILTRATING SOIL. (HYDRAULIC SOIL GROUP D)

NOTES:

- CONCRETE WASHOUT LOCATION SHALL BE APPROVED BY ENGINEER.
- SIZE OF EXCAVATION AND COMPACTED TRAP MUST BE COMMENSURATE WITH
- WASHOUT REQUIREMENTS FOR DAILY CONSTRUCTION ACTIVITIES.

 3. CONTRACTOR SHALL INSTALL A SIGN INDICATING THE CONCRETE WASHOUT AREA.
- 4. CONTRACTOR SHALL MAINTAIN WASHOUT AREA TO REMOVE MATERIALS BEYOND
- 75% CAPACITY.5. WASHOUT AREA SHALL NOT BE PLACED WITHIN 50' OF STORM DRAINS, OPEN
- DITCHES OR BODIES OF WATER.
- 6. CONTRACTOR SHALL INSPECT WASHOUT AREA AS NECESSARY TO PREVENT LEAKS AND OVER TOPPING.
- 7. WASHOUT AREA SHALL BE REMOVED AFTER CONSTRUCTION IS COMPLETE.

CONCRETE WASHOUT



KEY NOTES

- BURY UPSTREAM END OF MAT IN A TRENCH 6" WIDE BY 6" DEEP AND STAPLED IN STAGGERED ROWS ACROSS THE WIDTH.
- FOR JOINING ENDS OF ROLLS, OVERLAP END OF UP SLOPE MAT A MINIMUM OF 6" OVER

 DOWN SLOPE MAT (SHINGLE STYLE). USE A DOUBLE ROW OF STAGGERED STAPLES 4"

 APART
- MATS ON SIDE SLOPES SHALL OVERLAP A MINIMUM OF 6" OVER THE MAT BELOW (SHINGLE STYLE). STAPLE OVERLAP AT 12" INTERVALS.
- 4 THE OUTER EDGE ALONG SIDES OF THE MAT SHALL BE STAPLED EVERY 12".
- DOWNSTREAM (TERMINAL) END OF BLANKET SHALL BE STAPLED WITH A DOUBLE ROW OF STAGGERED STAPLES 12" APART.


NOTES:

- INSTALL EROSION MAT (EMAT) OVER WATERWAYS AS SHOWN IN THE EROSION CONTROL

 PLAN

 OF THE PROPERTY OF THE P
- 2. THE EMAT SHALL CONFORM TO WISDOT STANDARD SPECIFICATIONS SECTION 628.
- 3. PREPARE SOIL PRIOR TO INSTALLING EMAT, INCLUDING SEEDING AND FERTILIZING.
- 4. THE EMAT SHALL BE PLACED IN FIRM CONTACT WITH THE SOIL AND NOT BE ALLOWED TO BRIDGE OVER SURFACE IRREGULARITIES. THE MAT SHALL NOT BE STRETCHED.
- 5. START LAYING THE MATS BY ROLLING CENTER MAT IN THE DIRECTION OF FLOW, CENTERED ON THE CENTERLINE OF WATERWAY. THERE SHALL NOT BE AN OVERLAP OF MATS AT THE CENTER OF THE WATERWAY.
- 6. THE EMAT SHALL BE ANCHORED, OVERLAPPED, AND STAPLED ACCORDING TO MANUFACTURER'S INSTRUCTIONS. IF NO MANUFACTURER'S INSTRUCTIONS ARE AVAILABLE, INSTALL THE MAT AS FOLLOWS.
- 7. STAPLES SHALL BE "U" SHAPED, 0.12" DIAMETER WIRE OR GREATER (#11 GAUGE). (SEE STAPLE DETAIL FOR DIMENSIONS)
- 8. STAPLES ARE TO BE PLACED ALTERNATELY IN COLUMNS (IN THE DIRECTION OF THE WATERWAY) 2' APART AND IN ROWS (ACROSS THE WATERWAY) 3' APART THROUGHOUT THE AREA COVERED BY THE ECB.

EROSION MAT INSTALLATION




KEY NOTES:

- FOR MANUAL INSTALLATIONS, TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH, BACKFILL, AND COMPACT TRENCH WITH EXCAVATED SOIL.
- ② WOOD POST SHALL BE A MINIMUM SIZE OF 1 1/8" x 1 1/8" OF OAK OR HICKORY.
- 3 CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS.
 - A. TWIST METHOD OVERLAP THE END POSTS AND TWIST, OR ROTATE AT LEAST 180°.
- B. HOOK METHOD HOOK END OF EACH SILT FENCE LENGTH.

NOTES:

- 1. ATTACH FABRIC TO THE POSTS WITH WIRE STAPLES OR WOODEN LATH AND NAILS.
- 2. ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS.
- 3. 8'-0" POST SPACING ALLOWED IF A WOVEN GEOTEXTILE FABRIC IS USED.

SILT FENCE



SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

ANIM

TRUC

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT

K1 SITE

LA CRC	SSE		WISCONSIN	
	R	EVISION SCHEDULE		
DATE		DESCRIPTION	BY	
				L
				H
PROJECT	NO.	23-30331		
FILE NAM	IE	30331-C1-ERO	SION	
DRAWN BY		BDC		

BDC/SMW

KBR

ORIGINAL ISSUE DATE 03/28/2024

TITLE

DESIGNED BY


REVIEWED BY


CLIENT PROJECT NO.


EROSION CONTROL DETAILS


SHEET


C1-20


































FOR

RELIMINA

Z

SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT K1 SITE

LA CROSSE WISCONSIN **REVISION SCHEDULE** DATE DESCRIPTION PROJECT NO. 23-30331 FILE NAME 30331-C5-LAND

CLIENT PROJECT NO.

ORIGINAL ISSUE DATE 03/28/2024

DRAWN BY

TITLE

DESIGNED BY

REVIEWED BY

LANDSCAPE **DETAILS**

BDC


KBR

BDC/SMW

C5-30

PLANTING NOTES

- FOOTINGS, ETC.) WITH LOCATIONS OF PROPOSED LANDSCAPE ELEMENTS (FENCE. FOOTINGS, TREÉ ROOTBALLS, ETC.). CONTRACTOR SHALL REPORT ANY
- REMOVE ALL CONSTRUCTION DEBRIS AND MATERIALS INJURIOUS TO PLANT GROWTH
- REFER TO PLANTING DETAILS FOR AMENDED SOIL DEPTH IN PLANTING BEDS AND
- SURROUNDING TREES.
- REPRESENTATIVE RESERVES THE RIGHT TO REVISE PLANTING LAYOUT AT TIME OF INSTALLATION.
- INDICATED IN THE PLANT SCHEDULE.
- 7. IF DISCREPANCIES EXIST BETWEEN THE NUMBER OF PLANTS DRAWN ON THE PLANTING PLAN AND THE NUMBER OF PLANTS IN THE SCHEDULE, THE PLANTING PLAN SHALL GOVERN.
- 8. ANY PROPOSED SUBSTITUTIONS OF PLANT SPECIES SHALL BE MADE WITH PLANTS OF EQUIVALENT OVERALL FORM, HEIGHT, BRANCHING HABIT, FLOWER, LEAF, COLOR, FRUIT AND CULTURE, AND ONLY AFTER WRITTEN APPROVAL OF THE OWNER'S
- 9. ALL PLANT MATERIALS MUST CONFORM TO AMERICAN STANDARDS FOR NURSERY LISTED MAY BE USED IF THE STOCK CONFORMS TO ANSI Z60.1.
- AND HEALTHY GROWING CONDITION FOR ONE FULL GROWING SEASON (ONE YEAR) AFTER FINAL PROJECT ACCEPTANCE OR SHALL BE REPLACED BY THE CONTRACTOR FREE OF CHARGE WITH THE SAME GRADE AND SPECIES.
- 11. ALL TREES SHALL HAVE A STRONG CENTRAL LEADER. ANY TREES DEEMED NOT TO
- OPERATIONS. ANY AREAS THAT ARE DISTURBED SHALL BE RESTORED TO ITS
- AND WITHIN PLANTING BEDS TO A 3" MINIMUM DEPTH AS SHOWN IN TREE PLANTING DETAIL. DO NOT USE AN UNDERLAYMENT SUCH AS PLASTIC SHEET OR LANDSCAPE FABRIC. APPLY PRE-EMERGENT TO ALL PLANTING BEDS PRIOR TO MULCHING. REFER TO PLANS FOR ADDITIONAL DETAILS. REFER TO STORMWATER DETAILS FOR BASIN CONSTRUCTION AND MULCH APPLICATION.
- 15. CONTRACTOR SHALL PROVIDE SAMPLE OF MULCH TO BE APPROVED BY THE
- 16. INDICATED QUANTITIES ARE ESTIMATES AND SHALL BE CONFIRMED BY THE
- 17. ADJUST SPACING OF PLANT MATERIALS AROUND ADJACENT UTILITY STRUCTURES.



LANDSCAPE EDGING:

3/16"x4" WITH 3/16"x1'-4"

LANDSCAPE EDGING

1. COORDINATE LOCATION OF ALL UTILITIES (LINES, DUCTS, CONDUITS, SLEEVES, DISCREPANCIES TO OWNER'S REPRESENTATIVE PRIOR TO CONTINUING WORK.

SAVE AND PROTECT ALL EXISTING TREES NOT NOTED TO BE REMOVED. FROM PLANTING PITS AND BEDS PRIOR TO BACKFILLING WITH PLANTING MIX.

5. FIELD STAKE PLANTINGS ACCORDING TO PLAN. OWNER'S REPRESENTATIVE SHALL APPROVE ALL PLANT LOCATIONS PRIOR TO INSTALLATION. OWNER'S

6. ALL PLANT MATERIALS SHALL BE TRUE TO THEIR SCIENTIFIC NAME AND SIZE AS

STOCK (ANSI Z60.1), LATEST EDITION PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN, WASHINGTON D.C. LARGER SIZED PLANT MATERIALS OF THE SPECIES


10. ALL PLANT MATERIAL SHALL BE GUARANTEED BY THE CONTRACTOR TO BE IN A LIVE


HAVE A STRONG CENTRAL LEADER SHALL BE REJECTED. 12. CONTRACTOR IS RESPONSIBLE FOR ALL DAMAGE DUE TO CONSTRUCTION

ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE OWNER. 13. PROVIDE SHREDDED HARDWOOD MULCH SURROUNDING ALL PROPOSED TREES (5' Ø)

14. MULCHING MATERIAL SHALL BE SHREDDED HARDWOOD MULCH, WITH NO INDIVIDUAL PIECES LARGER THAN 3", FREE OF GROWTH OR GERMINATION INHIBITING INGREDIENTS, 3" MINIMUM DEPTH. MINIMUM DEPTHS AT LOCATIONS INDICATED ON

LANDSCAPE ARCHITECT.





5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.1 5.2 5.3 5.4 5.6 1.2 5.9 5.9 5.9 5.9 1.6 1.7 1.1 1.0 1.0 1.0 1.0 1.4 5.8 5.7 5.9 5.5 5.1 5.1 5.0 5.0 5.0 5.0 5.0 5.0 5.1 to 5.0 5.0 5.1 5.4 5.4 1.0 1.0 1.3 2.2 2.8 2.4 2.1 2.2 2.2 2.1 2.3 2.1 2.7 3.0 2.5 1.6 1.2 2.5 5.9 5.2 5.1 5.1 5.1 5.0 5.0 5.0 5.0 5.0 √5.1 5.1 5.8 5.8 5.1 5.1 5.1 5.8 5.8 2.7 1.5 1.3 3.1 5.5 8.8 6.7 3.7 2.3 2.2 3.1 7.0 5.1 6.3 3.5 1.6 1.1 1.7 □B7 5.4 5.2 5.1 5.0 5.0 5.0 5.0 5.0 6.0 5.0 5.0 5.0 5.1 5.1 5.2 5.3 5.日B 1.4 1.3 1.4 3.5 (5.3 7.日B 3.2 3.) 3.1 3.1 (3.0 5.4 中7.9 5.9 4.0 1.8 1.1 2.9 1.2 5.5 5.2 5.1 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.1 5.3 5.2 5.4 5.9 5.8 5.2 5.4 5.9 5.8 5.2 5.4 5.9 5.8 5.2 5.4 5.5 5.2 5.4 5.5 5.2 5.2 5.2 5.2 5.2 5.2 5.3 5.9 5.3 5.9 5.3 5.9 5.3 5.9 5.7 5.7 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 \$\dot 0.0 5\dot 0.0 5.0 5.0 5.0 5.0 5.0 5.0 5.1 5.1 5.2 5.6 2.2 1.5 1.4 2.5 2.8 2.4 2.2 2.2 2.7 2.8 2.5 2.1 2.5 2.7 2.8 1.8 3 2.2 1.3 5.5 5.2 5.1 5.0 5.0 5.0
 5.0
 5.0
 5.0
 5.0
 5.1
 5.3
 5.2
 5.3
 5.2
 5.3
 5.2
 5.8
 1.8
 1.9
 3.0
 3.9
 4.2
 3.2
 3.0
 2.2
 2.1
 2.7
 2.9
 4.3
 4.5
 3.3
 2.3
 1.4
 2.8
 1.3
 5.5
 5.2
 5.1
 5.0
 5.0
 5.0 5.0 5.0 5.0 5.0 5.0 5.1 6.2 5.5 9.4 2.8 6.7 1.4 3.5 6.3 8.1 4.7 3.9 3.05.0 5.0 5.0 5.0 5.0 5.0 5.0 5.1 5.4 5.3 5.6 5.5 5.6 5.2 5.0 5.3 5.8 5.4 5.9 5.3 5.1 5.9 5.4 5.3 5.8 5.8 5.9 5.8 5.6 5.3 5.1 5.1 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.2 1.2 1.3 1.3 1.2 1.4 1.4 1.6 1.4 1.6 1.5 1.4 1.6 1.5 1.7 1.71.3 1.4 1.3 1.9 1.4 0.6 0.3 0.2 0.2 0.2 0.0 0.0
 5.0
 5.0
 5.0
 5.0
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1
 5.1</t to the total transfer transfer to the total transfer t 5.0 δ.0 δ.0 δ.0 δ.0 δ.0 φ.0 δ.0 δ.0 δ.0 δ. 4 0.7 0.1 0.0 0.0 to 2 to 3 to 5.0 to 5.0 to 5.0 .1 0.1 0.0 0.0 0.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 √\$.0 5.0 5.0 5.0 5.0 3 0.4 0.1 0.0 0.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 b.0 5.0 5.0 5.0 to.4 to.1 to.0 to.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 t.1 t.1 t.0 t.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 . b.2 b.1 b.1 b.0 1 0.1 0.1 0.1 0.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 \$.0 \$.0 5.1 5.1 to 5.0 5.0 5.0 5.0 5.0 5.0 5.0 5.0 <u>6.0 5.0 5.0</u>

SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT

K1 SITE

LA CRO	SSE		WISCONSIN	
	R	EVISION SCHEDUI	LE	1
DATE		DESCRIPTION	BY	
				1
				ł
				1
				1
				1
				1
				1
				Ⅎ
PROJECT	NO.	23-30331		
FILE NAME 30331-E2-L		30331-E2-LIG	GHT	1

BDC

KBR

ORIGINAL ISSUE DATE 03/28/2024

BDC/SMW

TITLE

DRAWN BY

DESIGNED BY

REVIEWED BY

CLIENT PROJECT NO.

PHOTOMETRIC PLAN

SHEET


E2-00


CALCULATION SUMMARY

Label Calc Type Units Avg Min Max Avg/Min Max/Min

PARKING LOT ILLUMINANCE FC 2.93 1.1 9.8 2.66 8.91

	LIGHT FIXTURE SCHEDULE										
Lŧ	bel	Manufacturer	Catalog Number	Description	Lamp	Mounting/Pole Heig	ht Lamp Lumens	LLF	Watts (120-277V)	Quantity	Remarks
	Α	ARCHITECTURAL AREA LIGHTING (CURRENT)	SLD2-PM-2S-NL-80L-70-3K7-4F-UNV-CTS	LED DECORATIVE PENDANT AREA LIGHT	LED	18'	7800	0.9	69	12	THREE FIXTURES AT 90 DEGREE ORIENTATIONS.
	В	ARCHITECTURAL AREA LIGHTING (CURRENT)	SLD2-PM-2S-NL-80L-25-3K7-2-UNV-BC-CTS	LED DECORATIVE PENDANT AREA LIGHT	LED	18'	3300	0.9	25	4	
	С	FORMS+SURFACES	LBLCB-604-RGBW	BOLLARD	LED	N/A	520	0.9	11.4	16	
	D	TIVOLI	STRING: TCSL-S-X-24-120 ENGINE: ALS-TF-T25-E26-4W-XXK-6PK-R	STRING CATENARY LIGHT	LED	10'	400/ENGINE	0.9	4/ENGINE	212	





• This product qualifies as a "designated country

Agreements effective 04/23/2020.

5 year warranty

construction material" per FAR 52.225-11 Buy American-Construction Materials under Trade

Rev 10/12/23

TYPE A AND B

aal_sld_pendant_spec_R01

Current @

Example: SLD2-PM-2S-AF-80I-25-4K7-2-UNV-BLS AP Amber Phosphor 4W Type 4 Wide **27K8** 2700K 80CRI **4F** Type 4 Forward **3K7** 3000K 70 CRI **5QW** Type 5 Square Wide 3K8 3000K 80CRI 35K8 3500K 80CRI 3 Type 3 **4K7** 4000K 70CRI 4W Type 4 Wide 4K8 4000K 80CRI 4F Type 4 Forward **5K7** 5000K 70CRI 5QW Type 5 Square Wide 5K8 5000K 80CRI FR Front Row 5W Type 5 Wide 5QN Type 5 Square Narrow 5QM Type 5 Square Medium 5RW Type 5 Rectangular C Corner Optic Timer Based BLT Black Matte Textured DBS Dark Bronze Gloss Smooth DBT Dark Bronze Matte Textured GTT Graphite Matte Textured LGS Light Gray Gloss Smooth LGT Light Gray Matte Textured PSS Platinum Silver Gloss Smooth VGT Verde Green Matte Textured WHS White Gloss Smooth

© 2022 HLI Solutions, Inc. All rights reserved. Information and specifications subject to change without notice. All values are design or typical values when measured under laboratory condition

FORMS+SURFACES®

LIGHT COLUMN BOLLARD

PRODUCT DATA

LIGHT COLUMN BOLLARD

Light Column Bollards integrate into a wide range of settings and offer numerous design possibilities. Sleek in stainless steel, bollard columns are available in 5" or 6" diameters. Illumination options include LED lamps in white or RGBW, and multiple ways to direct light: no shield for symmetrical

MATERIAL & CONSTRUCTION DETAILS

CONFIGURATIONS	MATERIALS & FINISHES	LED LAMPS & DRIVER
Light Column Bollards are available in two sizes. Series 500 columns	Illuminated bollards have a tubular stainless	Custom LED light engine with Cree® LEDs.
are 5" (127 mm) diameter tubular stainless steel; Series 600 columns are 6" (152 mm) diameter tubular stainless steel.	steel column, white-frosted acrylic lens, and a stainless steel head cap.	Features advanced LED technology with 3000K warm white and 4000K natural white LEDs.
To complement the illuminated bollard, a non-illuminated version is also available in both Series 500 and Series 600.	Non-illuminated bollards are tubular stainless steel with welded stainless steel cap.	• 10W LED driver input power is 120-277V, -30°C starting temperature.
Bollards can be specified with a removable base, with the exception of the RGBW option.	Stainless steel is standard with a Satin finish and Ceramiloc treatment. See below for details	Driver has forward-phase, reverse-phase and 0-10V dimming capabilites.
Weather resistant GFCl outlet for maintenance access is available for Series 600, illuminated, non-RGBW, non-security bollards.	For optional powdercoat colors see the Forms+Surfaces Powdercoat Chart. Custom RAL colors are available for an upcharge.	LED driver certifications include: IP66 (waterproof) enclosure, and Class 2 rated output (UL8750)
SHIELD OPTIONS	WEIGHT	RGBW LED LAMPS & DRIVER
Directional shields are available for Series 500 and Series 600	Series 500, illuminated: 30 lbs (14 kg); non-	RGBW LED board utilizing Cree® LEDs.
illuminated and RGBW bollards.	illuminated: 32-33 lbs (15 kg)	RGBW, 4000K white, and dynamic white via
 Four standard shield designs are available for an upcharge. Refer to page 2 for details. 	 Series 600, illuminated: 34 lbs (15 kg); non- illuminated: 34-39 lbs (15-18 kg) 	DMX512 protocol and onboard decoder interface. Controller to be provided by others.
Custom shield designs with either 180° or 360° coverage are also available.	Series 600, deep set security core, illuminated: 170 lbs (77 kg); non-illuminated: 177 lbs (80	96W LED driver with 100-277V input power, -30°C starting temperature.
	kg)	LED driver certifications include: IP66 (waterproof) enclosure, and Class 2 rated output (UL8750)

lighting, or 180° and 360° shields in standard or custom designs. Non-illuminated and security core variations, and matching Light Column Pathway

Bollards and Light Column Pedestrian Lighting, make it easy to create a cohesive look across functionalities.

CERAMILOC TREATMENT

Ceramiloc is an invisible surface treatment that offers significantly enhanced protection from weather and graffiti and increases the maintenance ease of stainless steel. Ceramiloc combines ceramic durability with an unparalleled ability to lock out water spots, fingerprints, graffiti and more. Patented technology bonds nanosilica particles to the surface of the stainless steel. The treatment minimally alters the surface appearance of the stainless and offers numerous benefits: • Easily Cleaned: The Ceramiloc treatment creates a surface that simultaneously resists fingerprints and is easy to clean. Water spots, grease marks and more can be quickly wiped away. It also creates an "anti-graffiti" surface - even permanent marker is easily removed with a clean microfiber towel and water. • Durable: Ceramiloc-treated materials are abrasion- and scratch-resistant. The treatment is permanent, UV stable, and will not degrade or discolor over time. • Environmentally Sound: The Ceramiloc treatment is a no-VOC, water-based process. Because Ceramiloc surfaces are so easily maintained, cleaning solutions and maintenance are kept to a minimum.

ISTALLATION & MAINTENANCE		
INSTALLATION	MAINTENANCE	
 Standard mounting is surface mount with 1/2"-13x18" J-bolt anchors. 1/2" thick stainless steel base plate is slotted for rotational capability. 	Metal surfaces can be cleaned as needed using a soft cloth or brush with warm water and a mild	
 Light Column Bollards, Series 600, in both illuminated and non-illuminated designs are available with an optional embedded security core that accommodates two mounting styles: deep set mounting achieves an S10-P1 security rating; shallow mounting achieves an S30-P1 security rating. 	detergent. Avoid abrasive cleaners.	
• All bollards, except for the RGBW option, can be specified with a removable base.		
RGBW bollards are connected via a daisy-chained hard-wired control signal in and out of each bollard.		
Installation of a surge protector as part of each units wiring is recommended.		
Stainless steel mounting hardware sold separately. Templates are available upon request.		
800.451.0410 www.forms-surfaces.com	FORMS+SURFACES	

T 800.451.0410 | www.forms-surfaces.com © 2023 Forms+Surfaces® | All dimensions are nominal. Specifications and pricing subject to change without notice. For the most current version of this document, please refer to our website at www.forms-surfaces.com.

page 1 of 7 | Rev. 08-11-23

TYPE C

LED drivers have output power over-voltage, over-current protection, and short circuit

Field replaceable surge protection device

provides 20kA protection meeting ANSI/ IEEE C62.41.2 Category C High and Surge Location

Category C3; Automatically takes fixture off-line for protection when device is compromised

© 2022 HLI Solutions, Inc. All rights reserved. Information and specifications subject to change without notice. All values are design or typical values when measured under laboratory conditions.

protection with auto recovery

currentlighting.com/aal

the entire luminous surface area to provide a low

glare appearance. Catalog logic found on page 2


class distributions and maximum pole spacing in

new applications with high powered LEDs. Strike optics are held in place with a polycarbonate bezel to mimic the appearance of the Micro

Strike Optics so both solutions can be combined on the same application. Catalog logic found on

Current @

Strike Optics (18L LED count) provide best in



SHEET NOT VALID UNLESS THIS TEXT IS COLOR.

TR

Z

OR

RELIMINA

TRUC

Z

THIS DOCUMENT IS THE PROPERTY OF I & S GROUP, INC. AND MAY NOT BE USED, COPIED OR DUPLICATED WITHOUT PRIOR WRITTEN CONSENT.

PROJECT

RIVER POINT K1 SITE

	KI 3			CONS
LA CRO	SSE	WISC	CONSIN	
	REVISION SC	HEDULE		
DATE	DESCR	IPTION	BY	
				OR
PROJECT	NO. 23-3	0331		
FILE NAM	E 30331	-E2-LIGHT		O

DRAWN BY BDC **DESIGNED BY** BDC/SMW **REVIEWED BY** KBR ORIGINAL ISSUE DATE 03/28/2024 CLIENT PROJECT NO.

TITLE

SITE ELECTRICAL **FIXTURES**

E2-01

COMMERCIAL STRING LIGHT

Page 2 of 10

TYPE D